

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	TRAINING	EROSION CONTROL	UTILITIES	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS			
	880		10	290			880		CY	COMMON EXCAVATION	203.15							
				15			300		CY	TRENCH EXCAVATION OF EARTH	204.20							
				1			15		CY	TRENCH EXCAVATION OF ROCK	204.21							
							1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22							
					4		4		CY	STRUCTURE EXCAVATION	204.25							
				100	4		104		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30							
	420						420		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10							
	750		10				760		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35							
	7				2		9		CWT	EMULSIFIED ASPHALT	404.65							
	1						1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50							
					322		322		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33							
					1		1		LS	SHORING SUPERSTRUCTURE	502.10							
					40		40		EACH	SHORING SUPERSTRUCTURE BEARINGS	502.11							
					19510		19510		LB	STRUCTURAL STEEL, ROLLED BEAM	506.50							
					1620		1620		LB	STRUCTURAL STEEL	506.60							
					1		1		LS	STRUCTURAL STEEL	506.75							
					57750		57750		LB	EPOXY COATED REINFORCING STEEL	507.17							
					1		1		LS	SHEAR CONNECTORS (2720 - 7/8" x 7")	508.15							
					1		1		LS	STRUCTURAL PAINTING, SHOP APPLIED	513.25							
					1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED	513.30							
					1		1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD	513.36							
					1		1		LS	SURFACE PREPARATION, SHOP	513.40							
					1		1		LS	SURFACE PREPARATION, FIELD	513.41							
					40		40		GAL	WATER REPELLENT, SILANE	514.10							
					104		104		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10							
					850		850		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20							
					1		1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10							
					1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20							
					40		40		EACH	BEARING DEVICE ASSEMBLY, PREFORMED FABRIC PAD	531.10							
				6			6		EACH	SANITARY SEWER MANHOLE	604.22							
	6						6		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40							
	2			2			4		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42							
	2						2		EACH	CAST IRON GRATE WITH FRAME, TYPE D	604.47							
				6			6		EACH	CAST IRON COVER WITH FRAME, SEWER	604.56							
			10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25							
			10				10		CY	STONE FILL, TYPE I	613.10							
	285						285		LF	VERTICAL GRANITE CURB	616.21							
	240						240		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28							
	5						5		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47							
	36						36		SF	DETECTABLE WARNING SURFACE	618.30							

PROJECT NAME: Springfield
PROJECT NUMBER: BHF 016-2(14)
FILE NAME: s06j004qpfbuilder PLOT DATE: 03/31/2009
PROJECT MANAGER: R. WHITCOMB DRAWN BY: D. PETERSON
DESIGNED BY: D. PETERSON CHECKED BY: C. CARLSON
QUANTITY SHEET #1 SHEET 4 OF 72