

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	TRAINING	EROSION CONTROL	UTILITIES	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				3						3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
				25						25		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
				272						272		LF	TEMPORARY TRAFFIC BARRIER	621.90				
				216						216		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
							61			61		LF	PVC SEWER PIPE (6")(SDR 35)	628.35				
							22			22		LF	PVC SEWER PIPE (8")(SDR 35)	628.35				
							237			237		LF	PVC SEWER PIPE (12")(SDR 35)	628.35				
							11			11		LF	PVC SEWER PIPE (18")(SDR 35)	628.35				
							1			1		LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42				
				5						5		EACH	ADJUST ELEVATION OF VALVE BOX	629.20				
				100						100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
				1500						1500		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
					520					520		HR	EMPLOYEE TRAINEESHIP	634.10				
				1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
				1						1		LS	TRAFFIC CONTROL	641.10				
				2						2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
				1518						1518		LF	DURABLE 4 INCH WHITE LINE	646.400				
				1154						1154		LF	DURABLE 4 INCH YELLOW LINE	646.410				
				39						39		LF	DURABLE 6 INCH WHITE LINE	646.420				
				123						123		LF	DURABLE 24 INCH STOP BAR	646.480				
				55						55		EACH	DURABLE LETTER OR SYMBOL	646.490				
				73						73		LF	DURABLE CROSSWALK MARKING	646.500				
				285						285		LF	PAINTED CURB	646.81				
				3152						3152		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
							20			20		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							10			10		LB	SEED	651.15				
							10			10		LB	SEED, WINTER RYE	651.17				
							100			100		LB	FERTILIZER	651.18				
							0.25			0.25		TON	AGRICULTURAL LIMESTONE	651.20				
							0.25			0.25		TON	HAY MULCH	651.25				
				10			20			30		CY	TOPSOIL	651.35				
							1			1		LS	EPSC PLAN	652.10				
							50			50		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							10			10		CY	VEHICLE TRACKING PAD	653.35				

PROJECT NAME: **Springfield**  
PROJECT NUMBER: **BHF 016-2(14)**  
FILE NAME: s06j004qnbuilder PLOT DATE: 03/31/2009  
PROJECT MANAGER: R. WHITCOMB DRAWN BY: D. PETERSON  
DESIGNED BY: D. PETERSON CHECKED BY: C. CARLSON  
QUANTITY SHEET #2 SHEET 5 OF 72

N.A.B.I - NOT A BID ITEM