

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES								
														ROADWAY	EROSION CONTROL	BRIDGE	ALTERNATE A	ALTERNATE B	FULL C.E. ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
														1							1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
																4					4	CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
														1							1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
																2					2	CY	STRUCTURE EXCAVATION	204.25				
																12					12	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
																1210					1210	SF	PERMANENT STEEL SHEET PILING (MIN. SECTION MODULUS = 33.8 IN <sup>3</sup> )	505.35				
																1750					1750	LB	STRUCTURAL STEEL	506.60				
																225					225	LB	REINFORCING STEEL	507.15				
																38					38	LF	DRILLING AND GROUTING DOWELS	507.16				
																3					3	GAL	WATER REPELLENT, SILANE	514.10				
																3.20					3.20	MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20				
																6.70					6.70	MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED	522.25				
																0.50					0.50	MFBM	NON - STRUCTURAL LUMBER-UNTREATED	522.30				
																1					1	LS	STRUCTURAL GLUED LAMINATED TIMBER (10.7 MFBM) (LONGITUDINAL BEAMS)	522.40				
																1					1	CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
																4					4	SY	REPAIRING STONE MASONRY	602.40				
																			1		1	LS	FIELD OFFICE-ENGINEERS	631.10				
																			1		1	LS	TESTING EQUIPMENT - CONCRETE	631.16				
																			3000		3000	DL	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.26				
																1					1	LS	MOBILIZATION / DEMOBILIZATION	635.11				
																1					1	LS	TRAFFIC CONTROL	641.10				
																70					70	SY	GEOTEXTILE FOR SILT FENCE	649.51				
																80					80	SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
																10					10	LB	SEED	651.15				
																10					10	LB	FERTILIZER	651.18				
																0.25					0.25	TON	AGRICULTURAL LIMESTONE	651.20				
																0.50					0.50	TON	HAY MULCH	651.25				
																10					10	CY	TOPSOIL	651.35				
																1					1	LS	EPSC PLAN	652.10				
																40					40	HR	MONITORING EPSC PLAN	652.20				
																1					1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
																133					133	SY	TEMPORARY EROSION MATTING	653.20				
																130					130	LF	PROJECT DEMARCATION FENCE	653.55				
																1					1	LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10				
																1					1	LS	TIMBER PAINTING, FIRE RETARDANT	660.20				
																1					1	LS	TIMBER PAINTING, INSECTICIDE / FUNGICIDE	660.30				
																200					200	SY	METAL ROOFING	661.10				
																23					23	SF	TRAFFIC SIGNS, TYPE A	675.20				
																14					14	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
																2					2	EACH	REMOVING SIGNS	675.50				

PROJECT NAME: **RANDOLPH**  
PROJECT NUMBER: **BHO 1444(53)**  
FILE NAME: s06j092qs.dgn  
PROJECT MANAGER: **M. SARGENT**  
DESIGNED BY: **J. WEAVER**  
QUANTITY SHEET #1  
PLOT DATE: 11/8/2010  
DRAWN BY: **C. WEEBER**  
CHECKED BY: **M. SARGENT**  
SHEET 3 OF 27