

GENERAL NOTES

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE STATE OF VERMONT AGENCY OF TRANSPORTATION (VTRANS) STANDARD SPECIFICATIONS FOR CONSTRUCTION, DATED 2006 AND ITS LATEST REVISIONS AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), DATED 2003 AND ITS LATEST REVISIONS.
2. ALL SIGNS WITHIN THE PROJECT LIMITS ARE TO BE REPLACED UNLESS OTHERWISE NOTED OR AS DIRECTED BY THE RESIDENT ENGINEER. ALL NEW SIGNS SHALL BE IN ACCORDANCE WITH THESE PLANS, APPLICABLE VTRANS E-SERIES STANDARDS OR AS DIRECTED BY THE RESIDENT ENGINEER. SIGN LOCATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE, EXACT LOCATIONS TO BE DETERMINED BY THE RESIDENT ENGINEER IN THE FIELD.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE TO PRIVATE OR PUBLIC PROPERTY BEYOND THAT SHOWN ON THE PLANS CAUSED BY THE CONTRACTOR, AT THE SOLE COST OF THE CONTRACTOR.
4. ALL FORMED 2" SQUARE STEEL SHAPED POSTS SHALL BE FABRICATED WITH 12 GAUGE STEEL WITH A MINIMUM YIELD OF 55 KSI. NO FLANGE CHANNEL SUBSTITUTIONS WILL BE ALLOWED.
5. ALL REMOVED SIGNS AND POSTS FROM THIS PROJECT SHALL BE STOCKPILED AT THE VERMONT AGENCY OF TRANSPORTATION- DISTRICT 1- EAST DORSET FACILITY FOR FUTURE MAINTENANCE PURPOSES FOR USE BY DISTRICT FORCES. SEE THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

PROJECT NAME:	MANCHESTER-PAWLET	FILE NAME:	STP_SIGN_PROJECT.dgn	PLOT DATE:	22-APR-2009 16:4
PROJECT NUMBER:	STPG_SIGN_(14)	PROJECT LEADER:	N.AVERY	DRAWN BY:	ROADWAY
		DESIGNED BY:	N.AVERY	CHECKED BY:	
GENERAL NOTES				SHEET	_3_ OF _60_