STATE OF VERMONT
AGENCY OF TRANSPORTATION

COMPOSITE QUANTITY SHEET 1

MONTPELIER NH 2604(I)						MONTPELIER STP 2618(I)			TOTALS		DESCRIPTIONS			
ROADWAY	ROADWAY (NO STATE/FEDERAL PARTICIPATION)	EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
44	10					2			56		CY	COMMON EXCAVATION	203.15	-
25	8								33		CY	SOLID ROCK EXCAVATION	203.16	-
						50			50		CY	EARTH BORROW	203.30	-
4661									4661		LF	SHOULDER BERM REMOVAL	203.40	-
1						1			2		CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.22	-
51887				1613		17300			70800		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
30	10								40		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	-
114						96			210		TON	AGGREGATE SHOULDER, RAP	402.13	-
217				3		72			292		CWT	EMULSIFIED ASPHALT	404.65	-
1						1			2		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
5968	850			112		2150			9080		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-
1						1			2		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				215					215		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
				100					100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-
1						1			2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
27						4			31		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
27						3			30		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
26						3			29		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
26						11			37		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
60						25			85		HR	POWER GRADER RENTAL	608.15	-
60						25			85		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-
40						15			55		HR	POWER BROOM RENTAL, TYPE I	608.30	-
60						25			85		HR	POWER BROOM RENTAL, TYPE II	608.31	-
60						25			85		HR	TRUCK RENTAL	608.37	-
60						25			85		HR	LOADER RENTAL, TYPE I	608.40	-
2						0.75			2.75		MGAL	DUST CONTROL WITH WATER	609.10	-
			15				2		17		CY	STONE FILL, TYPE I	613.10	-
283	107								390		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	-
276	107								383		LF	REMOVAL OF EXISTING CURB	616.41	-
175	60								235		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	-
230									230		SF	DETECTABLE WARNING SURFACE	618.30	-
8						6			14		EACH	YIELDING MARKER POSTS	619.17	-
37.5						875			912.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
						225			225		LF	STEEL BEAM GUARDRAIL, GALVANIZED WITH 8 FEET POSTS	621.205	-
						2			2		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
3						2			5		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
151									151		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: MONTPELIER
PROJECT NUMBER: NH 2604(I) / STP 2618(I)

FILE NAME: p06b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p06b034cqs01.i

PLOT DATE: 03-AUG-2011 14:06
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 3 OF 84