



SECTION

HANDWORK DETAILS FOR PAVED DRIVES

SECTION A-A

HANDWORK DETAILS FOR GRAVEL DRIVES

STATION	POSITION	QUANTITY (SY)
NH 2604(I)		
U.S. ROUTE 2		
108+17	LT	16
109+37	LT	18
111+32	LT	20
112+85	LT	20
118+75	RT	15
120+80	RT	16
121+32	RT	12
121+85	RT	12
122+94	RT	12
123+91	RT	13
124+67	RT	13
125+84	RT	40
127+80	RT	8
128+47	RT	10
128+72	RT	10
129+36	RT	11
130+39	RT	10
131+00	RT	11
131+70	RT	10
132+19	RT	10
132+87	RT	9
136+27	RT	10
136+90	RT	7
138+01	RT	21
139+00	RT	8
139+99	RT	15
141+54	RT	32
143+61	RT	8
146+75	RT	12
147+73	RT	8
150+00	RT	12

STATION	POSITION	QUANTITY (SY)
NH 2604(I)		
U.S. ROUTE 2 CONT.		
158+89	RT	17
159+00	LT	25
160+72	LT	24
161+42	RT	23
161+46	LT	7
163+44	LT	14
164+98	RT	24
166+29	LT	28
167+00	LT	31
167+11	RT	16
168+37	LT	21
169+44	LT	52
170+97	LT	19
171+07	RT	12
172+39	LT	62
172+77	RT	12
173+48	RT	10
175+40	LT	68
175+78	RT	17
176+35	LT	14
177+43	LT	8
178+26	RT	10
179+69	RT	15
221+48	RT	21
224+44	RT	36
225+21	LT	51
226+08	RT	23
226+84	RT	22
228+84	RT	14
230+04	RT	20
231+16	RT	24

NOTES:

- PAVING LIFT NOT TO EXCEED 2" (50mm)
- THE COST OF PLACING SUBBASE MATERIAL, CLEANING EXISTING PAVED SURFACES, INCLUDING POWER EQUIPMENT, AND FOR FILLING JOINTS, CRACKS AND HOLES WILL NOT BE PAID DIRECTLY BUT WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675.
- EXCAVATION NEEDED TO ACHIEVE PROPER DRIVE SLOPES WILL NOT BE PAID DIRECTLY BUT WILL BE CONSIDERED INCIDENTAL TO ITEM 900.675.

LEGEND



NOT TO SCALE

**DRIVE
DETAIL
SHEET**

PROJECT NAME: MONTPELIER	PLOT DATE: 03-AUG-2011 14:07
PROJECT NUMBER: NH 2604(I)	DRAWN BY: STANTEC
FILE NAME: p06b034.dgn	CHECKED BY: JLL
DESIGNED BY: STANTEC	SHEET 17 OF 84
IPARM FILE: p06b034ds.i	