



- 604.412, 604.415 OR 604.418 REHAB. DIS, CBS OR MHS, CLASS I, II OR III
 STA. 89+27, LT STA. 91+40, RT
 STA. 89+27, RT STA. 91+73, RT
 STA. 90+35, LT
 STA. 90+37, RT
- 616.28 CAST-IN-PLACE CONCRETE CURB, TYPE B
 STA. 90+68 TO STA. 90+83, LT
 STA. 91+40 TO STA. 91+61, LT
- 616.41 REMOVAL OF EXISTING CURB
 STA. 90+68 TO STA. 90+83, LT
 STA. 91+40 TO STA. 91+61, LT
- 618.10 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH
 STA. 90+68 TO STA. 90+83, LT
 STA. 91+40 TO STA. 91+61, LT
- 618.30 DETECTABLE WARNING SURFACE
 STA. 89+57, LT
 STA. 90+79, LT
 STA. 91+40, LT
- 646.402 DURABLE 4 INCH WHITE LINE, THERMOPLASTIC
 STA. 89+00 TO 92+00, SOLID LT & RT
 (INCLUDING EDGE LINE BREAKS FOR TOWN HIGHWAYS)
 STA. 89+00 TO 90+80, SOLID LT (LANE LINE)
 STA. 90+87, DOUBLE SOLID LT (VSECU)
 STA. 91+34, DOUBLE SOLID RT (HIGH SCHOOL)
 STA. 91+88 TO 92+00, SOLID RT (LANE LINE)
- 646.412 DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC
 STA. 89+00 TO 90+80, DOUBLE SOLID RT
 STA. 90+87, DOUBLE SOLID LT (VSECU)
 STA. 91+34, DOUBLE SOLID RT (HIGH SCHOOL)
 STA. 91+88 TO 92+00, DOUBLE SOLID CL
- 646.482 DURABLE 24 INCH STOP BAR, THERMOPLASTIC
 STA. 91+07, LT (VSECU)
 STA. 91+61, RT (HIGH SCHOOL)
- 646.492 DURABLE LETTER OR SYMBOL, THERMOPLASTIC
 STA. 90+22, LT - ARROW
 STA. 90+62, LT - ONLY
 STA. 91+05, LT - ARROW
 STA. 91+15, LT - ARROW
 STA. 91+53, RT - ARROW
 STA. 91+61, RT - ARROW
 STA. 91+90, LT - SCHOOL
 STA. 91+92, RT - ARROW
 STA. 91+92, RT - ARROW
- 646.502 DURABLE CROSSWALK MARKING, THERMOPLASTIC
 STA. 89+57, LT & RT
 STA. 90+87, LT
 STA. 91+34, RT
- 646.512 DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC
 STA. 90+20, RT
- 646.602 TEMPORARY 4 INCH WHITE LINE, PAINT
 STA. 89+00 TO 92+00, SOLID LT & RT
 (INCLUDING EDGE LINE BREAKS FOR TOWN HIGHWAYS)
 STA. 89+00 TO 90+80, SOLID LT (LANE LINE)
 STA. 90+87, DOUBLE SOLID LT (VSECU)
 STA. 91+34, DOUBLE SOLID RT (HIGH SCHOOL)
 STA. 91+88 TO 92+00, SOLID RT (LANE LINE)
- 646.612 TEMPORARY 4 INCH YELLOW LINE, PAINT
 STA. 89+00 TO 90+80, DOUBLE SOLID RT
 STA. 90+87, DOUBLE SOLID LT (VSECU)
 STA. 91+34, DOUBLE SOLID RT (HIGH SCHOOL)
 STA. 91+88 TO 92+00, DOUBLE SOLID CL
- 646.682 TEMPORARY 24 INCH STOP BAR, PAINT
 STA. 91+07, LT (VSECU)
 STA. 91+61, RT (HIGH SCHOOL)
- 646.692 TEMPORARY LETTER OR SYMBOL, PAINT
 STA. 90+22, LT - ARROW
 STA. 91+05, LT - ARROW
 STA. 91+15, LT - ARROW
 STA. 91+53, RT - ARROW
 STA. 91+61, RT - ARROW
 STA. 91+90, LT - SCHOOL
 STA. 91+92, RT - ARROW
 STA. 91+92, RT - ARROW
- 646.702 TEMPORARY CROSSWALK MARKING, PAINT
 STA. 89+57, LT & RT
 STA. 90+87, LT
 STA. 91+34, RT
- 646.712 TEMPORARY RAILROAD CROSSING SYMBOL, PAINT
 STA. 90+20, RT
- 675.50 REMOVING SIGNS (TYPE A)
 AS SHOWN - 17
- 675.60 ERECTING SALVAGED SIGNS
 AS SHOWN - 3

NOTE:
 1. FOR LEGENDS, SEE LAYOUT SHEET #1.
 2. ALL EXISTING SIGNS NOT SHOWN SHALL BE RETAINED AS DIRECTED BY THE RESIDENT ENGINEER.



NOT TO SCALE
PROJECT LAYOUT SHEET #2

PROJECT NAME: MONTPELIER
 PROJECT NUMBER: NH 2604(I)
 FILE NAME: p06b034.dgn
 PROJECT LEADER: JLL
 DESIGNED BY: MCF
 IPARM FILE: p06b034i02.i
 PLOT DATE: 03-AUG-2011 4:07
 DRAWN BY: STANTEC
 CHECKED BY: JLL
 SHEET 19 OF 84