STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
234+22, RT					12.0		~~1~~ ~~1~~ ~~1~~				1			X	X															MOUNT SALVAGED SIGNS ON NEW POST OFFSET 2 FEET FURTHER RIGHT THAN SALVAGED OBJECT MARKER AT STA. 234+00, RT	- - -	- - -
	TOTAL - THIS SHEET				12.0		~~3~~							~~23~~ 17																		
	SHEET 1 SUBTOTALS				~~48.60~~ 9.0		~~1~~ 3							~~102~~ 43.2																		
	SHEET 2 SUBTOTALS				~~31.22~~ 45.67		2							~~80~~ 67.3																		
	SHEET 3 SUBTOTALS				~~60.70~~ 65.7		~~1~~ 2							~~102~~ 92.0																		
	SHEET 4 SUBTOTALS				~~36.67~~ 41.67		~~3~~ 2							~~92~~ 79.9																		
	SHEET 5 SUBTOTALS				~~39.05~~ 45.3		~~1~~							~~125~~ 82.4																		
	SHEET 6 SUBTOTALS				~~27.80~~ 40.3		~~2~~ 1							~~107~~ 89.8																		
	SHEET 7 SUBTOTALS				52.25		3							~~46~~ 31.0					85												
	SHEET 8 SUBTOTALS				81.85		0							~~120~~ 85.5																		
	SHEET 9 SUBTOTALS				~~80.20~~ 92.45		~~1~~							~~64~~ 50.8																		
	SHEET 10 SUBTOTALS				~~21.90~~ 38.55		~~5~~ 4							~~93~~ 77.8																		
	SHEET 11 SUBTOTALS				~~55.65~~ 65.65		~~3~~ 2							~~152~~ 92.4																		
	SHEET 12 SUBTOTALS				33.88		0							~~109~~ 61.2																		
	SHEET 13 SUBTOTALS				~~33.90~~ 59.15		1							~~90~~ 90.4																		
	SHEET 14 SUBTOTALS				~~51.90~~ 73.4		~~4~~ 1							~~114~~ 85.25																		
	SHEET 15 SUBTOTALS				~~22.18~~		~~3~~ 4							~~93~~ 80.4																		
	SHEET 16 SUBTOTALS				8.40		~~5~~ 6							~~122~~ 114.8																		
	SHEET 17 SUBTOTALS				22.28		~~1~~ 3							~~77~~ 185.0																		
	SHEET 18 SUBTOTALS				1.40		~~6~~							~~80~~ 115.0																		
	SHEET 19 SUBTOTALS				0		~~3~~							~~23~~ 17.0																		
	PROJECT SUBTOTALS				709.83		~~45~~ 34							1791					85												
	ROUNDING				1.17		-							9					-												
												FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB						
	TOTALS				SF ~~711~~ 926.34	SF	EA. ~~45~~ 34	SF						FT ~~1800~~ 1541.15					LB 85		EA.		LB			EA.	EA.	LB			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: NH 2604(1)

FILE NAME: p06b034.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p06b034tss19.i

PLOT DATE: 03-AUG-2011 14:10
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 57 OF 84