STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
		1			1		LS	TRAFFIC CONTROL (STP 2618(I))	641.10	-			
		0.25			0.25		LS	PUBLIC RELATIONS OFFICER	641.12	-			
		1			1		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
		8400			8400		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	70			
		9400			9400		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	95			
		425			425		LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	5			
		30			30		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-			
		20			20		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
		16700			16700		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	39			
		18700			18700		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	89			
		850			850		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	10			
		65			65		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	5			
		16			16		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
		900			900		EACH	LINE STRIPING TARGETS	646.76	4			
			10		10		SY	GEOTEXTILE UNDER STONE FILL	649.31	2			
		30			30		LB	SEED	651.15	EST.			
		250			250		LB	FERTILIZER	651.18	EST.			
		1			1		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
		25			25		CY	TOPSOIL	651.35	EST.			
			1950		1950		SY	TEMPORARY EROSION MATTING	653.20	41			
		47			47		SF	TRAFFIC SIGNS, TYPE A	675.20	0.91			
		265			265		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	4			
		27			27		EACH	REMOVING SIGNS (TYPE A)	675.50	-			
		17			17		EACH	ERECTING SALVAGED SIGNS	675.60	-			
		2			2		EACH	DELINEATOR WITH STEEL POST	676.10	-			
		2			2		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
		1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
		930			930		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	8			

PROJECT NAME: MONTPELIER
PROJECT NUMBER: STP 2618(I)

FILE NAME: p06d114.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p06d114qs02.i

PLOT DATE: 03-AUG-2011 4:11
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 70 OF 84