STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 1+156 LT	EATON PL						1				1			~~4.6~~ 3.96		4.6		X																		
	STOP	1	750	750	0.56																													R1-1		E-143
STA 1+162 LT	NO OUTLET	1	750	750	0.56						1			~~4.6~~ 3.96		4.6		X																W14-2		
STA 1+181 RT		1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																W11-2 FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																												W16-7P FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+190 LT		1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																W11-2 FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																												W16-7P FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+221 LT	SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 4.27		4.6		X																R2-1		E-142
STA 1+243 LT	RUTLAND 31	1	1825	300	0.55						2			4.27 ~~9.2~~ 4.27			9.2	X																D1-1		E-123
	WEST	1	600	300	0.18																												M3-4		E-136A
	4	1	600	600	0.36																												M1-4		E-136A
STA 1+244 RT	ONLY	1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																VR-921		E-145A
STA 1+249 LT	MOUNTAIN AVE						1				1			~~4.6~~ 4.27		4.6		X																SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP	1	750	750	0.56																												R1-1		E-143
											m	m	m	41.4	m	41.4	m		EA	kg	kg	kg		kg	kg	kg	kg								
														37.81																						
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."		**TOTALS**	m^2 5.26	m^2	EA. 2	m^2			m ~~41.4~~		m 41.4			kg	EA.	kg			EA.	EA.	kg																

TRAFFIC SIGN SUMMARY SHEET 2

PROJECT : WOODSTOCK	PROJECT NO. : NH 2606(I)S
DESIGN FILE NAME: /pave/06b036/pb036.dgn	
IPARM FILE NAME: pb036ts02.i	PLOT DATE: 11-JUN-2012 16:1
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 08-2006
SQUAD LEADER: PTS	DRAWN BY: MRS
CLD 06-0232	SHEET: 43 OF 73