STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 1+261 LT	RIVER ST						1				1			~~4.6~~ 4.27		4.6		X																	SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 0040 1424 0581	1 1	750 150	750 250	0.56 0.04																												R1-1 (BACK TO BACK)		E-143 E-138
STA 1+272 LT	LEGAL LOAD LIMIT 16,000 POUNDS	1	600	750	0.45						1			~~4.6~~ 4.27		4.6		X																	VR-017		E-141
STA 1+366 LT		1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																	W1-2MCL		
STA 1+384 RT	NO OUTLET	1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																	W14-2		
STA 1+402 RT	CHURCH ST EXT						1				1			~~4.6~~ 4.27		4.6		X																	SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 0040 1424 0589	1 1	750 150	750 250	0.56 0.04																												R1-1 (BACK TO BACK)		E-143 E-138
STA 1+428 LT	R	1	300	300	0.09						1			~~4.6~~ 3.66		4.6		X																	R8-3A		E-143
STA 1+444 RT	SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 3.66		4.6		X																	R2-1		E-142
STA 1+460 RT	BIKE ROUTE	1	600	450	0.27						1			~~4.6~~ 4.27		4.6		X																	D11-1		
		1	300	225	0.07																														M7-2		
STA 1+470 RT	COLLEGE HILL						1				1			~~4.6~~ 4.27		4.6		X																	SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP	1	750	750	0.56																												R1-1		E-143
STA 1+472 LT	R	1	300	300	0.09						1			~~4.6~~ 3.66		4.6		X																	R8-3A		E-143
												m	m	m 46.0	m	m 46.0	m		EA	kg	kg	kg		kg	kg	kg	kg							
														40.87																						
TOTALS		m² 4.30	m²	EA. 3	m²							m ~~46.0~~			m 46.0					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 3

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036ts03.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 44 OF 73