STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
	OPTION ITEMS																																			
STA 1+654 RT	STOP 0040 1424 0605	1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																R1-1 (BACK TO BACK)		E-143 E-138
		1	150	250	0.04																														
STA 1+659 LT	RESERVED PARKING	1	300	450	0.14						1			~~4.6~~ 4.57		4.6		X																	60	
	30 MIN PARKING 8:00 AM TO 5:00 PM →	1	300	450	0.14																												R7-108		
MOVED TO I+807 RT ~~STA 1+680 RT~~ PLACED ON TOP OF ROUTE SIGNS	~~SO. WOODSTOCK 5~~	1	1825	300	0.55						2			4.27 ~~8.2~~ 4.27		8.2		X																D1-1		E-123
	WHITE RIVER JCT 14	1	1825	300	0.55																												D1-1		E-123
	SPRINGFIELD 26	1	1825	300	0.55																												D1-1		E-123
STA 1+694 LT	NO PARKING ANY TIME →	1	300	450	0.14						1			~~4.6~~ 4.12		4.6		X																R7-1		
	30 MIN PARKING 8:00 AM TO 5:00 PM ←	1	300	450	0.14																												R7-108		
STA 1+703 RT MOVED TO I+784 RT ~~STA 1+719 RT~~	~~REMOVED AT THE REQUEST OF THE TOWN~~	1	~~600~~	~~600~~	0.36						1			~~4.6~~ 3.96		4.6		X																R3-2		E-143
	BIKE ROUTE	1	600	450	0.27						1			~~4.6~~ 3.96		4.6		X																D11-1		
		1	300	225	0.07																												M7-2		
STA 1+734 RT	STOP	1	750	750	0.56						1			~~4.6~~ 3.96		4.6		X																R1-1		E-143
STA 1+748 LT	YIELD 900 X 900 X 900	1			0.35						1			~~4.6~~ 3.96		4.6		X																R1-2		E-146
STA 1+750 LT	DOG WASTE WARNING						1				1			~~4.6~~ 3.66		4.6		X																		
												m	m	45.0 41.0	m	45.0	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 4.42	m²	EA. 1	m²							m ~~45.0~~			m 45.0					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 5

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036ts05.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 46 OF 73