STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 1+841 RT	REMOVED AT REQUEST OF TOWN	1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X															W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+859 RT	ONLY	1	750	750	0.56						1			~~4.6~~ 3.96		4.6		X															VR-921		E-145A
STA 1+895 RT	SOUTH PARK ST						1				1			~~5.0~~ 4.57			5.0	X															SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN.		
	COURT ST						1																										SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP	1	750	750	0.56																											R1-1		E-143
	0040 1424 0619	1 1	600 150	600 250	0.36 0.04																											R3-2 (BACK TO BACK)		E-143 E-138
STA 1+896 LT	ONE WAY	1	900	300	0.27						1			~~4.6~~ 3.66		4.6		X															R6-1R		E-142
STA 1+913 RT	RESERVED PARKING	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X																60	
STA 1+902 RT	REMOVED AT REQUEST OF TOWN	1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X															W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."												m	m	m 28.0 24.99	m	m 23.0	m 5.0		EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS			m² 3.41	m²		EA. 2	m²				m ~~28.0~~			m 28.0					kg			EA.	kg				EA.	EA.	kg					

TRAFFIC SIGN SUMMARY SHEET 7

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036ts07.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 48 OF 73