STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
~~STA 1+923 RT~~ MOVED TO STA 1+982 RT	ELIMINATED ~~SO. WOODSTOCK 5~~	1	1825	300	0.55						2			~~3.81~~ ~~8.2~~ 3.81		8.2		X															D1-1		E-123
	WHITE RIVER JCT 14	1	1825	300	0.55																												D1-1		E-123
	BETHEL 18	1	1825	300	0.55																												D1-1		E-123
STA 1+925 LT	TO	1	600	300	0.18						2			~~4.88~~ ~~9.6~~ 4.88		9.6		X															M4-5		E-136B
	NORTH EAST SOUTH	1 1 1	600 600 600	300 300 300	0.18 0.18 0.18																											3	M3-1 M3-2 (SIGN FRAMES E-123) M3-3		E-136B E-136A E-136B
	VERMONT 12 4 VERMONT 12	1 1 1	600 600 600	600 600 600	0.36 0.36 0.36																												M1-4		E-136B E-136A E-136B
		1 1 1	525 525 525	375 375 375	0.20 0.20 0.20																												M5-1 M6-3 M6-3		E-136B E-136A E-136B
STA 1+947 RT	RESERVED PARKING	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X																60	
STA 1+954 LT	WEST	1	600	300	0.18						1			~~4.6~~ 4.88		4.6		X															M3-4		E-136A
	4 DO NOT ENTER	1 1	600 750	600 750	0.36 0.56																												M1-4 R5-1 (BACK TO BACK)		E-136A E-143
		1 1	525 600	375 600	0.20 0.36																												R3-4 (BACK TO BACK)	60	E-143
STA 1+966 RT	BIKE ROUTE	1	600	450	0.27						1			~~4.6~~ 3.97		4.6		X															D11-1		
		1	300	225	0.07																												M7-1		
STA 1+972 RT	20 MINUTE BUS PARKING TO DROP OFF AND PICK UP PASSENGERS PLEASE SHUT OFF ENGINES						1				1			~~4.6~~ 4.27		4.6		X																	
												m	m	m 36.2	m	m 36.2	m		EA	kg	kg	kg		kg	kg	kg	kg								
														34.16																					
TOTALS		m² 6.19	m²	EA. 1	m²							m ~~36.2~~			m 36.2					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 8

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036ts08.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 49 OF 73