STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

LAST Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
	WHITE RIVER JCT 14 BETHEL 18 SUICIDE SIX SKI AREA																																MOVED FROM 1+923 RT		
																																	OPTION ITEMS		
STA 1+982 RT	← SUICIDE SIX SKI AREA	1	1800	300	0.54						1						~~4.6~~	~~X~~					1	~~49.8~~ 49.08	14.25	= 4.34						D1-1	60	E-123
	NORTH EAST	1 1	600 600	300 300	0.18 0.18																										2	M3-1 M3-2 (SIGN FRAMES E-123)		E-136B E-136A
	VERMONT 12 4	1 1	600 600	600 600	0.36 0.36																											M1-4		E-136B E-136A
	← ↑	1 1	525 525	375 375	0.20 0.20																											M6-1 M6-3		E-136B E-136A
	P PARKING	1	750	600	0.45																											D4-1		
STA 2+015 LT	WEST	1	600	300	0.18						1			~~4.6~~ 4.12		4.6		X														M3-4		E-136A
	4	1	600	600	0.36																											M1-4		E-136A
STA 2+022 LT	NO PARKING ANY TIME ←	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X														R7-1		
STA 2+036 LT	BIKE ROUTE	1	600	450	0.27						1			~~4.6~~ 3.96		4.6		X														D11-1		
	↑	1	300	225	0.07																											M7-2		
STA 2+040 RT	DO NOT ENTER	1	750	750	0.56						1			~~4.6~~ 4.88		4.6		X														R5-1		E-143
		1	600	600	0.36																											R3-4		E-143
STA 2+046 RT	TO	1	600	300	0.18						2			4.88 ~~9.6~~ 4.88		9.6		X														M4-5		E-136B
	EAST SOUTH	1 1	600 600	300 300	0.18 0.18																										2	M3-2 M3-3 (SIGN FRAMES E-123)		E-136A E-136B
	4 VERMONT 106	1 1	600 750	600 600	0.36 0.45																											M1-4		E-136A E-136B
	↶ ↶	1 1	525 525	375 375	0.20 0.20																												60 60		
												m	m	m 28.0 26.38	m	m 28.0	m 4.6		EA	kg	kg	kg		kg	kg	kg	kg 49.8							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	m²	m²	EA.	m²		m	m	kg	EA.	kg	EA.	EA.	kg
	6.16					~~28.0~~ 0	28.0 4.6		1	0 49.8			

TRAFFIC SIGN SUMMARY SHEET 9

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036ts09.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 50 OF 73