STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																											
2+180 RT STA ~~2+203 LT~~	MOVED TO TO	1	600	300	0.18						2			4.88 ~~10.2~~ 4.88			10.2	X															M4-5		E-136B
	SOUTH EAST WEST	1 1 1	600 600 600	300 300 300	0.18 0.18 0.18																												3	M3-3 M3-2 (SIGN FRAMES E-123) M3-4		E-136B E-136A E-136A
	VERMONT 106 4 4	1 1 1	750 600 600	600 600 600	0.45 0.36 0.36																													M1-4 M1-4		E-136B E-136A E-136A
		1 1 1	525 525 525	375 375 375	0.20 0.20 0.20																													M5-1 M5-1 M6-3		E-136B E-136A E-136A
STA 2+248 RT	DOG WASTE WARNING						1				1			~~4.6~~ 3.66		4.6		X																		
STA 2+249 RT	STOP	1	750	750	0.56						1			~~4.6~~ 3.97		4.6		X																R1-1		E-143
STA 2+291 RT	REMOVED AT REQUEST OF TOWN	1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X																W11-2 FLUORESCENT YELLOW-GREEN SHEETING		E-152
	REMOVED AT REQUEST OF TOWN	1	600	300	0.18																													W16-7P FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+299 LT	STOP	1	750	750	0.56						1			~~4.6~~ 3.96		4.6		X																R1-1		E-143
STA 2+301 RT	TO TO	1 1	600 600	300 300	0.18 0.18						2			4.57 ~~9.6~~ 4.88		9.6		X																M4-5 M4-5		E-136A E-136B
	WEST EAST SOUTH	1 1 1	600 600 600	300 300 300	0.18 0.18 0.18																												3	M3-4 M3-2 (SIGN FRAMES E-123) M3-3		E-136A E-136A E-136B
	4 4 VERMONT 106	1 1 1	600 600 750	600 600 600	0.36 0.36 0.45																													M1-4 M1-4		E-136A E-136A E-136B
		1 1 1	525 525 525	375 375 375	0.20 0.20 0.20																													M6-1 M6-1 M6-1		E-136A E-136A E-136A
												m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
														38.2		28.0	10.2	4																
														35.37																				
TOTALS		m² 7.02	m²	EA. 1	m²		m ~~38.2~~				m 38.2								kg	EA.	kg		EA.	EA.	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 11

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036tsll.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 52 OF 73