STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 2+438 LT	REMOVED AT REQUEST OF TOWN	1	750	750	0.56						1			~~4.6~~ 4.57		4.6			X														W11-2 FLUORESCENT YELLOW-GREEN SHEETING		E-152
	REMOVED AT REQUEST OF TOWN	1	600	300	0.18																											W16-7P FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+446 LT		1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X															R7-1		
STA 2+447 RT	CENTRAL ST						1				1			~~4.6~~ 4.57		4.6		X															SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN.		
	HIGH ST						1																										SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	0040 1424 0636	1 1	750 150	750 250	0.56 0.04						1			~~4.6~~ 4.57		4.6		X															R1-1 (BACK TO BACK)		E-143 E-138
STA 2+514 LT	BOND ST						1				1			~~4.6~~ 3.97		4.6		X																	
STA 2+517 LT		1	750	750	0.56						1			~~4.6~~ 3.97		4.6		X															R1-1		E-143
STA 2+523 RT SAT 2+529 LT		2	750	750	0.56 ~~1.12~~ 0.56						1 1			~~4.6~~ ~~4.6~~		4.6 4.6		 X	X														W11-2 FLUORESCENT YELLOW-GREEN SHEETING		E-152
	NOT INSTALLED PAY FOR SIGN	2	600	300	0.18 ~~0.36~~ 0.18																											W16-7P FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+550 LT	SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 3.97		4.6		X															R2-1		E-142
STA 2+559 RT	NO PARKING LOADING ZONE	1	300	450	0.14						1			~~4.6~~ 4.57		4.6		X															R7-6		
STA 2+586 RT	LINCOLN ST						1				1			~~4.6~~ 3.96		4.6		X															SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	0040 1424 0644	1 1	750 150	750 250	0.56 0.04																											R1-1 (BACK TO BACK)		E-143 E-138
TOTALS		m² 4.71	m²	EA. 4	m²							m ~~50.6~~				m 50.6				kg	EA.	kg					EA.	EA.	kg					
												m	m	m 50.6	m	m 50.6	m		EA 2	kg	kg	kg		kg	kg	kg	kg						
														37.81																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 13

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036tsl3.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 54 OF 73