STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 2+589 RT STA 2+591 LT	REMOVED AT REQUEST OF TOWN	2	750	750	0.56 ~~1.12~~ 0.56						1 1			4.57 ~~4.6~~ ~~4.6~~ 4.27		4.6 4.6		X X															W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
	REMOVED AT REQUEST OF TOWN	2	600	300	0.18 ~~0.36~~ 0.18																										W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+618 RT	SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 3.96		4.6		X													R2-1			E-142
STA 2+657 RT	NO PARKING ANY TIME ←	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X													R7-1			
STA 2+664 LT	SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 3.97		4.6		X													R2-1			E-142
STA 2+673 LT	TO	1	600	300	0.18						2			4.88 ~~9.6~~ 4.57		9.6		X													M4-5			E-136B
	SOUTH EAST	1 1	600 600	300 300	0.18 0.18																										M3-3 M3-2	(SIGN FRAMES E-123)	2	E-136B E-136A
	VERMONT 12 4	1 1	600 600	600 600	0.36 0.36																										M1-4			E-136B E-136A
	↑ ↑	1 1	525 525	375 375	0.20 0.20																										M6-3 M6-3			E-136B E-136A
STA 2+686 LT	STOP	1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X													R1-1			E-143
STA 2+686 LT STA 2+686 RT		2	750	750	0.56 ~~1.12~~ 0.56						1 1			4.57 ~~4.6~~ ~~4.6~~ 3.97		4.6 4.6		X X													W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		2	600	300	0.18 ~~0.36~~ 0.18																										W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+696 LT		1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X													W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																										W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
												m	m	m 51.0 47.56	m	m 51.0	m	EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m² 6.96	m²	EA.	m²				m ~~51.0~~			m 51.0				kg	EA.	kg		EA.	EA.	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 14

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036tsl4.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 55 OF 73