STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 2+712 LT	BIKE ROUTE	1	600	450	0.27						1			~~4.6~~ 3.96		4.6		X																D11-1		
	←	1	300	225	0.07																													M7-1		
STA 2+718 LT	P PARKING ↗	1	750	600	0.45						1			~~4.6~~ 4.27		4.6		X																D4-1		
	4 HR P PARKING ←	1	750	600	0.45																													D4-1		
STA 2+738 RT	NO PARKING ANY TIME →	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X																R7-1		
2+760 RT STA ~~2+749 RT~~	MOVED TO SPEED LIMIT 25	1	600	750	0.45						1			~~4.6~~ 3.96		4.6		X																R2-1		E-142
STA 2+765 LT	SUICIDE SIX SKI AREA ↑	1	1800	300	0.54						2			5.18 ~~10.2~~ 5.18		10.2		X																D1-1	60	E-123
	TO	1	600	300	0.18																													M4-5		E-136B
	WEST / NORTH	1 1	600 600	300 300	0.18 0.18																											2	M3-4 M3-1 (SIGN FRAMES E-123)		E-136A E-136B
	4 / VERMONT 12	1 1	600 600	600 600	0.36 0.36																													M1-4		E-136A E-136B
	↖ / ↑	1 1	525 525	375 375	0.20 0.20																													M6-2 M6-3		E-136A E-136B
STA 2+772 RT	STOP 0040 1424 0656	1 1	750 150	750 250	0.56 0.04						1			~~4.6~~ 3.96		4.6		X																R1-1 (BACK TO BACK)		E-143 E-138
STA 2+773 RT	FORD ST						1				1			~~4.6~~ 3.51		4.6		X																SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN.		
	PLEASANT ST						~~1~~																													
2+755 RT STA ~~2+782 RT~~	MOVED TO ®	1	300	300	0.09						1			~~4.6~~ 3.81		4.6		X																R8-3a		E-143
STA 2+848 RT	NO PARKING ANY TIME ←	1	300	450	0.14						1			~~4.6~~ 3.66		4.6		X																R7-1		
												m	m	m 47.0 41.15	m	m 47.0	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 4.86	m²	EA. ~~2~~ 1	m²							m ~~47.0~~			m 47.0					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 15

PROJECT :	PROJECT NO. :
WOODSTOCK	NH 2606(I)S

DESIGN FILE NAME: /pave/06b036/pb036.dgn
IPARM FILE NAME: pb036tsl5.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 56 OF 73