STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
STA 2+869 RT		1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																	W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																													W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+876 LT		1	750	750	0.56						1			~~4.6~~ 4.27		4.6		X																	W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																													W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+969 RT		1 1	750 150	750 250	0.56 0.04						1			~~4.6~~ 3.96		4.6		X																	R1-1 (BACK TO BACK)		E-143 E-138
STA 2+969 RT							1				1			~~4.6~~ 3.20		4.6		X																	SALVAGE SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF SIGN.		
							1																														
STA 3+040 RT		1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X																	W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																													W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 3+041 LT		1	750	750	0.56						1			~~4.6~~ 4.57		4.6		X																	W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																													W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 3+050 RT		1	300	450	0.14						1			~~4.6~~ 3.96		4.6		X																	R7-4			
							1																														
STA 3+079 LT		1	600	750	0.45						1			~~4.6~~ 3.96		4.6		X																	R2-1			E-142
												m	m	m 36.8	m	m 36.8	m	EA	kg	kg	kg		kg	kg	kg	kg								
														32.76																						
TOTALS		m² 4.15	m²	EA. 3	m²							m ~~36.8~~			m 36.8				kg	EA.	kg		EA.	EA.	kg										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 16

PROJECT : WOODSTOCK	PROJECT NO. : NH 2606(I)S
DESIGN FILE NAME: /pave/06b036/pb036.dgn	
IPARM FILE NAME: pb036tsl6.i	PLOT DATE: 11-JUN-2012 16:1
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 08-2006
SQUAD LEADER: PTS	DRAWN BY: MRS
CLD 06-0232	SHEET: 57 OF 73