STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																						
STA 12+~~055~~ 8 RT	RESERVED PARKING	1	300	450	0.14						1			~~4.6~~	USED EXIST. POST	4.6			X															73	
STA 12+057 RT STA 12+063 LT		2	750	750	0.56 ~~1.12~~ 0.56						2			4.57 ~~9.2~~ 4.57		9.2			X														W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
REMOVED AT REQUEST OF TOWN		2	600	300	0.18 ~~0.36~~ 0.18																		REMOVED AT REQUEST OF TOWN									W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 12+185 LT	TO / TO	1 1	600 600	300 300	0.18 0.18						2			4.27 + 9.3	4.27	9.3		X														M4-5 M4-5		E-136A E-136B
	WEST / SOUTH	1 1	600 600	300 300	0.18 0.18																										1	M3-4 M3-3 (SIGN FRAMES E-123)		E-136A E-136B
	4 / VERMONT 106	1 1	600 750	600 600	0.36 0.45																											M1-4		E-136A E-136B
	0120 1424 0011	1	150	250	0.04																													E-138
STA 12+205 RT STA 12+213 LT		2	750	750	0.56 ~~1.12~~ 0.56						2			4.27 ~~9.2~~ 4.42		9.2		X																W11-2	FLUORESCENT YELLOW-GREEN SHEETING		E-152
		2	600	300	0.18 ~~0.36~~ 0.18																											W16-7P	FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 12+226 RT	STOP	1	750	750	0.56						1			3.96 ~~4.6~~		4.6		X														R1-1		E-143
STA 12+226 RT	NORTH	1	600	300	0.18						1			4.57 ~~4.6~~		4.6		X														M3-1		E-136B
	VERMONT 12	1	600	600	0.36																													E-136B
		1	525	375	0.20																											M6-1		E-136B
TOTALS		m² 5.97	m²	EA.	m²							m ~~41.5~~	m	m 41.5	m	m 41.5	m		EA 3	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					

m m 41.5 m m 41.5 m EA 3 kg kg kg kg kg kg kg

34.90 m

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 1

PROJECT :	PROJECT NO. :
WOODSTOCK	STP 2509(I)S

DESIGN FILE NAME: /pave/05c056/pc056.dgn
IPARM FILE NAME: pc056ts01.i PLOT DATE: 11-JUN-2012 16:
SURVEYED BY: CLD ENGINEERS INC SURVEY DATE: 08-2006
SQUAD LEADER: PTS DRAWN BY: MRS
CLD 06-0232 SHEET: 70 OF 73