

COMPOSITE QUANTITY SHEET 1

WATERBURY STP 2607 (1)				WATERBURY STP 2201 (1)					TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	NON PARTICIP.	FULL C.E.	ROADWAY	BRIDGE	EROSION CONTROL	NON PARTICIP.	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS	
2									2	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-				
9									9	CY	COMMON EXCAVATION	203.15	-				
8									8	CY	SOLID ROCK EXCAVATION	203.16	-				
1				1					2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-				
4100				49100					53200	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-				
9									9	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	-				
				11					11	TON	SUBBASE, RAP	301.40	-				
45				405					450	TON	AGGREGATE SHOULDERS, RAP	402.13	-				
17				200					217	CWT	EMULSIFIED ASPHALT	404.65	-				
1				1					2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-				
500				5625					6125	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-				
1				1					2	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-				
				1					1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-				
				1					1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-				
				1					1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-				
					270				270	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-				
					100				100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-				
2				1					3	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-				
6				17					23	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-				
2				4					6	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-				
2							1		3	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-				
16				85					101	HR	POWER GRADER RENTAL	608.15	-				
16				85					101	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-				
7				25					32	HR	POWER BROOM RENTAL, TYPE I	608.30	-				
11				45					56	HR	POWER BROOM RENTAL, TYPE II	608.31	-				
11				45					56	HR	TRUCK RENTAL	608.37	-				
11				45					56	HR	LOADER RENTAL, TYPE I	608.40	-				
						250			250	CY	STONE FILL, TYPE I	613.10	-				
						50			50	CY	STONE FILL, TYPE II	613.11	-				
50									50	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	-				
				1040					1040	LF	TREATED TIMBER CURB	616.35	-				
50				45					95	LF	REMOVAL OF EXISTING CURB	616.41	-				
				1					1	EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-				
60									60	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	-				
48									48	SF	DETECTABLE WARNING SURFACE	618.30	-				
2				34					36	EACH	YIELDING MARKER POSTS	619.17	-				
650				4175					4825	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-				

PROJECT NAME: WATERBURY / WATERBURY
PROJECT NUMBER: STP 2607(1) / STP 2201(1)
FILE NAME: p99b154.dgn PLOT DATE: 10-JAN-2011
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: STANTEC
IPARM FILE: p99b154cqs01.i SHEET 3 OF 49