

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	EROSION CONTROL	NON PARTICIP.	FULL C.E.		GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
	2					2	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-			COLD PLANING, BITUMINOUS PAVEMENT
	9					9	CY	COMMON EXCAVATION	203.15	0.5	3797	SY	MAINLINE
	8					8	CY	SOLID ROCK EXCAVATION	203.16	1.0	188	SY	SIDE ROADS
	1					1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.	115	SY	ROUNDING
	4100					4100	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	115	4100	SY	TOTAL
	9					9	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	0.5			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
	45					45	TON	AGGREGATE SHOULDERS, RAP	402.13	4	333	TON	MAINLINE WEARING COURSE (TYPE IVS)
	17					17	CWT	EMULSIFIED ASPHALT	404.65	0.4	17	TON	SIDE ROADS WEARING COURSE (TYPE IVS)
	1					1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.	116	TON	LEVELING (TYPE IVS)
	500					500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	34	34	TON	ROUNDING
	1					1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	EST.	500	TON	TOTAL
	2					2	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-			
	6					6	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
	2					2	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
	2					2	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-			
	16					16	HR	POWER GRADER RENTAL	608.15	EST.			
	16					16	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
	7					7	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
	11					11	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
	11					11	HR	TRUCK RENTAL	608.37	EST.			
	11					11	HR	LOADER RENTAL, TYPE I	608.40	EST.			
	50					50	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	8.8			
	50					50	LF	REMOVAL OF EXISTING CURB	616.41	8.8			
	60					60	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	9.3			
	48					48	SF	DETECTABLE WARNING SURFACE	618.30	-			
	2					2	EACH	YIELDING MARKER POSTS	619.17	-			
	650					650	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	21			
	2					2	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
	617					617	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
	4					4	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
	600					600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
	1800					1800	HR	FLAGGERS	630.15	EST.			
					0.5	0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-			
					0.5	0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
					0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
					1500	1500	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
	0.5					0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-			

PROJECT NAME: WATERBURY  
 PROJECT NUMBER: STP 2607(I)  
 FILE NAME: p06b038.dgn PLOT DATE: 14-DEC-2010  
 PROJECT LEADER: JLL DRAWN BY: STANTEC  
 DESIGNED BY: STANTEC CHECKED BY: STANTEC  
 IPARM FILE: p06b038qs01.1 SHEET 9 OF 49