

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES							TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	BRIDGE	EROSION CONTROL	NON PARTICIP.	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS		
3540					3540	HR	FLAGGERS	630.15	EST.					
				0.5	0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-			GEOTEXTILE UNDER STONE FILL		
				0.5	0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	-	942	CY	DITCHING		
				0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-	135	CY	EROSION REPAIR		
				1500	1500	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-	8	CY	ROUNDING		
0.5					0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-	1085	CY	TOTAL		
1					1	LS	TRAFFIC CONTROL (STP 2201(I))	641.10	-					
0.5					0.5	LS	PUBLIC RELATIONS OFFICER	641.12	-					
3					3	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-					
18800					18800	LF	DURABLE 4 INCH WHITE LINE, TYPE I TAPE	646.401	122					
19900					19900	LF	DURABLE 4 INCH YELLOW LINE, TYPE I TAPE	646.411	126					
1060					1060	LF	DURABLE 6 INCH WHITE LINE, TYPE I TAPE	646.421	16					
85					85	LF	DURABLE 6 INCH YELLOW LINE, TYPE I TAPE	646.431	1					
3800					3800	LF	DURABLE 8 INCH WHITE LINE, TYPE I TAPE	646.441	21					
510					510	LF	DURABLE 8 INCH YELLOW LINE, TYPE I TAPE	646.451	9					
430					430	LF	DURABLE 24 INCH STOP BAR, TYPE I TAPE	646.481	9					
167					167	EACH	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	-					
70					70	LF	DURABLE CROSSWALK MARKING, TYPE I TAPE	646.501	4					
37500					37500	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	354					
39900					39900	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	352					
2110					2110	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	22					
170					170	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	2					
7600					7600	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	42					
1010					1010	LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	8					
850					850	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	8					
334					334	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-					
135					135	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	3					
1120					1120	EACH	LINE STRIPING TARGETS	646.76	11					
540					540	LF	PAINTED CURB	646.81	4					
9800					9800	SF	PAINTED ISLAND	646.82	27					
				1085	1085	SY	GEOTEXTILE UNDER STONE FILL	649.31	8					
				87	87	LB	SEED	651.15	EST.					
				500	500	LB	FERTILIZER	651.18	EST.					
				2	2	TON	AGRICULTURAL LIMESTONE	651.20	EST.					
				2	2	TON	HAY MULCH	651.25	EST.					
				50	50	CY	TOPSOIL	651.35	EST.					
				430	430	SY	TEMPORARY EROSION MATTING	653.20	3					

PROJECT NAME: WATERBURY  
PROJECT NUMBER: STP 2201(I)  
FILE NAME: p99b154.dgn  
PROJECT LEADER: JLL  
DESIGNED BY: STANTEC  
IPARM FILE: p99b154qs02.1  
PLOT DATE: 10-JAN-2011  
DRAWN BY: STANTEC  
CHECKED BY: STANTEC  
SHEET 25 OF 49