

ITEM DETAIL SUMMARY SHEET

LOCATION			GUARDRAIL					MISCELLANEOUS											REMARKS												
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.206	621.60	621.70	621.71	621.80	301.40	402.13	604.412	604.415	613.10	613.11	616.35	616.41	617.10	619.17		649.31	676.10	676.12									
			S.B. GALV. LF	S.B.C.R. GALV. NESTED LF	ANCHOR FOR S.B. RAIL EA	G.R. APP. SECTION GALV. TYPE I EA	G.R. APP. SECTION GALV. TYPE II EA	REMOVAL & DISPOSAL OF GUARDRAIL LF	SUBBASE, RAP TON	AGG. SHLDRS., RAP TON	REHAB DI. CB, OR MH, CLASS I EA	REHAB DI. CB, OR MH, CLASS II EA	STONE FILL, TYPE I CY	STONE FILL, TYPE II CY	TREATED TIMBER CURB LF	REMOVAL OF EXIST. CURB LF	RELOC. MAILBOX, SNGL. SUPP. EACH	YIELDING MARKER POSTS EACH		GEO. UNDER STONE FILL SY	DEL. W/ STEEL POST EACH	REMOVAL OF EXIST. DEL. EACH									
VT ROUTE 100																															
WATERBURY																															
0+21.2	87+12.0	LT&RT								399	17	4		50				34				QUANTITIES FOR USE AS DIRECTED BY THE RESIDENT ENGINEER.									
WATERBURY																															
2+19.0	14+94.0	RT	1277					1277														1	1	CONNECT TO EXISTING GUARDRAIL ON RAMP E @ VT 100 STA. 14+94.0, RT; INSTALL ANCHOR @ STA. 2+19.0, RT							
7+85	8+22	LT											38						135					ITEMS TO BE USED WITH SLOPE EROSION REPAIR							
12+89.5	17+77.0	LT	475					487.5						487.5										INSTALL TREATED TIMBER CURB @ STA. 12+89.5 TO 17+77, LT							
15+21.5	18+09.0	RT	239.5					277																1	1	INSTALL ANCHOR @ STA. 15+21.5, RT					
20+29.0	21+41.5	LT	64.5					104																	1	1	INSTALL ANCHOR @ STA. 21+41.5, LT				
20+62.0	21+37.0	RT	64.5					75																		1	1	INSTALL ANCHOR @ STA. 21+37.0, RT			
31+30	31+71	RT							10.6							41										REMOVE EXISTING GRANITE CURB, RT - SEE DETAIL ON MISCELLANEOUS DETAIL SHEET					
33+35.5	33+48.0	RT	14.5					12.5																		1		CONNECT TO EXISTING GUARDRAIL @ STA. 33+35.5, RT; INSTALL ANCHOR @ STA. 33+48.0, RT			
34+62.0	39+87.0	RT	527					525																			1	1	CONNECT TO EXISTING GUARDRAIL @ STA. 34+62.0, RT; INSTALL ANCHOR @ STA. 39+87.0, RT		
46+42.0	52+17.0	RT	579					575							545												2	1	INSTALL ANCHORS @ STA. 46+42.0, RT & STA. 52+17.0, RT; RELOCATE MAILBOX @ STA. 49+53, RT; INSTALL TREATED TIMBER CURB @ STA. 46+55 TO 52+00		
54+11.0	55+23.5	RT	116.5					100																			2	1	INSTALL ANCHORS @ STA. 54+11.0, RT & STA. 55+23.5, RT		
61+78.0	65+90.5	RT	416.5																								2		INSTALL ANCHORS @ STA. 61+78.0, RT & STA. 65+90.5, RT		
73+19.0	73+56.5	LT	39.5					39.5																			1	1	INSTALL ANCHOR @ STA. 73+19.0, LT		
73+56.5	73+81.5	LT		25.0																									SEE SPAN DETAIL		
73+81.5	74+06.5	LT	27.0																										INSTALL ANCHOR @ STA. 74+06.5 LT		
73+19.0	73+56.5	RT	39.5					39.5																					1	1	INSTALL ANCHOR @ STA. 73+19.0 RT
73+56.5	73+81.5	RT		25.0																										SEE SPAN DETAIL	
73+81.5	74+06.5	RT	27.0																											INSTALL ANCHOR @ STA. 74+06.5 RT	
78+32.0	80+94.5	RT	266.5					262.5																				1	2	INSTALL ANCHOR @ STA. 78+32.0, RT & STA. 80+94.5, RT	
*THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS.																															
SHEET SUBTOTALS:			4173.5	50	18	2	2	3774.5	10.6	399	17	4	38	50	1032.5	41	1	34	135	18	11	<div style="text-align: center;"> ITEM DETAIL SUMMARY SHEET </div>		PROJECT NAME: WATERBURY							
ROUNDING			1.5	-	-	-	-	25.5	0.4	6	-	-	-	-	7.5	4	-	-	-	-	-					PROJECT NUMBER: STP 2201(1)					
TOTALS:			4175	50	18	2	2	3800	11	405	17	4	38*	50	1040	45	1	34	135*	18	11					FILE NAME: p99b154.dgn					
																						PLOT DATE: 20-JAN-2011									
																						DRAWN BY: STANTEC									
																						CHECKED BY: STANTEC									
																						SHEET 27 OF 49									
																						IPARM FILE: p99b154idss.i									