STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS ( )																								
MANCHESTER INTERCHANGE 4: 8	BENNINGTON 24 → SOUTH	1 1	72 24	12 12	6.00 2.00						2			2@16' X																		X	SIGN ID CODE D1-1 SIGNS SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE M3-3		E-123 E-136A
	7	1	24	24	4.00																												SIGN ID CODE M1-4		E-136A
	→	1	21	15	2.19																												SIGN ID CODE M6-1		E-136A
9	← RUTLAND 33 NORTH	1 1	72 24	12 12	6.00 2.00						2			2@16' X																		X	SIGN ID CODE D1-1 SIGNS SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE M3-1		E-123 E-136A
	7	1	24	24	4.00																												SIGN ID CODE M1-4		E-136A
	←	1	21	15	2.19																												SIGN ID CODE M6-1		E-136A
10	TO	1	24	12	2.00						2											2	193.8 ~~214~~	1@13.25' 1@12.25'								X	SIGN ID CODE M4-5		E-136A
	SOUTH NORTH	1 1	24 24	12 12	2.00 2.00																												SIGN ID CODE M3-3 SIGN ID CODE M3-1		E-136A E-136A
	7 7	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE M1-4 SIGN ID CODE M1-4		E-136A E-136A
	↑ →	1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-3 SIGN ID CODE M6-1		E-136A E-136A
11	EAST WEST	1 1	24 24	12 12	2.00 2.00						2			2@14'								~~2~~	~~176~~								X	SIGN ID CODE M3-2 SIGN ID CODE M3-4		E-136B E-136B
	VERMONT 11 VERMONT 30	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE M1-5 SIGN ID CODE M1-5		E-136B E-136B
												LF	LF	LF - 92 ~~(56)~~	LF	LF - (56)	LF		EA.	LB	LB	LB		LB 193.8 ~~390~~	LB	LB	LB								
	TOTALS				SF 42.76	SF	EA.	SF				LF - (56) 92			LF - (56)					LB			EA. ~~1~~ 2	LB 193.8 ~~390~~				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #25

PROJECT NAME: MANCHESTER - DORSET
PROJECT NUMBER: NH 2608(1)S

FILE NAME: p06b040.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06b040tss25.i
PLOT DATE: 07-JUN-2010
DRAWN BY: K.A.R.
CHECKED BY: D.W.E.
SHEET 57 OF 78