STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																		REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in) lb/ft					W-SHAPE STEEL FTG. SIZE				SIGN FRAMES REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD	FOUNDATION	3.0	3.5	4.0	5.0	24"	30"	WEIGHT	POST SIZE				
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
												OPTION ITEMS ( )																							
	SHEET 33 SUBTOTALS				-	-	-					(42)		-	(42)	-								-	-	-			-	-	-				
	SHEET 34 SUBTOTALS				-	-	-					(56)		-	(56)	-								-	-	-			-	-	-				
	SHEET 35 SUBTOTALS				-	-	-					(14)		(14)	(14)	(14)								-	-	-			-	-	-				
	SHEET 36 SUBTOTALS				-	-	-					(84)		-	(84)	-								-	-	-			-	-	-				
	SHEET 37 SUBTOTALS				-	-	-					(112)		-	(112)	-								-	-	-			-	-	-				
	SHEET 38 SUBTOTALS				-	-	-					(112)		-	(112)	-								-	-	-			-	-	-				
	SHEET 39 SUBTOTALS				-	-	-					(28)		(14)	(28)	(14)								-	-	-			-	-	-				
	SHEET 40 SUBTOTALS				-	-	-					(14)		-	(14)	-								-	-	-			-	-	-				
	SHEET 41 SUBTOTALS				-	-	-					(70)		-	(70)	-								-	-	-			-	-	-				
	SHEET 42 SUBTOTALS				-	-	-					(42)		-	(42)	-								-	-	-			-	-	-				
	SHEET 43 SUBTOTALS				-	-	-					(14)		(28)	(14)	(28)								-	-	-			-	-	-				
	SHEET 44 SUBTOTALS				-	-	-					(28)		-	(28)	-								-	-	-			-	-	-				
	SHEET 45 SUBTOTALS				-	-	-					(42)		-	(42)	-								-	-	-			-	-	-				
	SHEET 46 SUBTOTALS				-	-	-					-		(28)	-	(28)								-	-	-			-	-	-				
	SHEET 47 SUBTOTALS				-	-	-					-		(14)	-	(14)								-	-	-			-	-	-				
	SHEET 48 SUBTOTALS				-	-	-					-		(56)	-	(56)								-	-	-			-	-	-				
	SHEET 49 SUBTOTALS				-	-	-					-		(28)	-	(28)								-	-	-			-	-	-				
	SHEET 50 SUBTOTALS				-	-	-					-		(70)	-	(70)								-	-	-			-	-	-				
	SHEET 51 SUBTOTALS				-	-	-					-		(42)	-	(42)								-	-	-			-	-	-				
	SHEET 52 SUBTOTALS				-	-	-					-		(-)	-	(-)								-	-	-			-	-	-				
	SHEET 53 SUBTOTALS				-	-	-					-		(42)	-	(42)								-	-	-			-	-	-				
	SHEET 54 SUBTOTALS				-	-	-					-		(98)	-	(98)								-	-	-			-	-	-				
	SHEET 55 SUBTOTALS				-	-	-					(14)		(56)	(14)	(56)								-	-	-			-	-	-				
	SHEET 56 SUBTOTALS				-	-	-					-		(28)	-	(28)								-	-	-			-	-	-				
	SHEET 57 SUBTOTALS				-	-	-					-		(56)	-	(56)								-	-	-			-	-	-				
	SHEET 58 SUBTOTALS				-	-	-					-		(14)	-	(14)								-	-	-			-	-	-				
	SUBTOTAL THIS SHEET				-	-	-					(672)		(588)	(672)	(588)								-	-	-			-	-	-				
	SHEET 59 SUBTOTALS				1246.49	957.00	1					-		1596	-	-								32	2844	907			2	4	1796				
	ROUNDING				0.51	-	-					(28)		(12)	(28)	(12)								-	56	43			-	-	104				
												-		54	-	-																			
												LF (700) -	LF	LF (600) 1650	LF (700) -	LF (600) -	LF		EA.	LB	LB	LB		LB 2900	LB 950	LB	LB								
	TOTALS	SF 1247	SF 957	EA. 1	SF							LF (1300) 1650			LF (1300) -					LB			EA. 32	LB 3850				EA. 2	EA. 4	LB 1900				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #28

PROJECT NAME: MANCHESTER - DORSET
PROJECT NUMBER: NH 2608(I)S

FILE NAME: p06b040.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06b040tss28.I
PLOT DATE: 07-JUN-2010 I
DRAWN BY: K.A.R.
CHECKED BY: D.W.E.
SHEET 60 OF 78