QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						3	3	EA	THINNING AND TRIMMING FOR SIGNS	201.31	EST
						650	650	CY	EARTH BORROW	203.30	-
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
						425	425	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	8.34
						12,000	12,000	TON	SUBBASE, RAP	301.40	-
						105,000	105,000	SY	RECLAIMED STABILZED BASE	310.20	1441.13
						130	130	TON	AGGREGATE SHOULDERS	402.12	-
						1,700	1,700	TON	AGGREGATE SHOULDERS, RAP	402.13	64
						435	435	CWT	EMULSIFIED ASPHALT	404.65	7.14
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
						17,500	17,500	CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	371.7
									*** BEGIN OPTION ITEMS AA ***		
						12,000	12,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% RAP CONTENT)	490.30	402.18
						12,000	12,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% < RAP CONTENT < 15.0%)	490.30	402.18
						12,000	12,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% ≤ RAP CONTENT < 25.0%)	490.30	402.18
						12,000	12,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% ≤ RAP CONTENT ≤ 50.0%)	490.30	402.18
									*** END OPTION ITEMS AA ***		
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					225		225	LF	REMOVAL OF EXISTING RAILING	525.10	12.5
					225		225	LF	BRIDGE RAILING REPAIR, TYPE I	525.50	12.5
						1	1	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
						1	1	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						1	1	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
						1	1	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
						2	2	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
						200	200	HR	POWER GRADER RENTAL	608.15	EST
						500	500	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						150	150	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
						70	70	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						1,000	1,000	HR	TRUCK RENTAL	608.37	EST
						200	200	HR	LOADER RENTAL, TYPE I	608.40	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
8644.39	TON	TYPE IVS
		SIDEROADS
85.70	TON	TYPE IVS
		LEVELING COURSE
2867.73	TON	TYPE IVS
402.18	TON	ROUNDING
12000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: TROY-NEWPORT
PROJECT NUMBER: STP 2613(1)

FILE NAME: 06B056.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET: 06b056*09.i

PLOT DATE: 25-OCT-2011 12:17
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 9 OF 31