QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						150	150	MGAL	DUST CONTROL WITH WATER	609.10	-
						0.4	0.4	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-
						510	510	CY	STONE FILL, TYPE I	613.10	11
						20	20	EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
						72	72	EACH	YIELDING MARKER POSTS	619.17	-
						3,000	3,000	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	90
						100	100	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-
						375	375	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	12.5
						23	23	EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
						8	8	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
						4	4	EACH	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-
						3,300	3,300	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	44
						650	650	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						4,000	4,000	HR	FLAGGERS	630.15	EST
						80	80	HR	FLAGGERS, RAILROAD	630.20	EST
			1				1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1				1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
				520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						2	2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						61,000	61,000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1632
						50,000	50,000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	3337
						185	185	LF	DURABLE 24 INCH STOPBAR, THERMOPLASTIC	646.482	8
						32	32	EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
						2	2	EACH	DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC	646.512	-
						122,000	122,000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	3264
						100,000	100,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	6674
						370	370	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	16
						64	64	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
						4	4	EACH	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	-
						2,750	2,750	EACH	LINE STRIPING TARGETS	646.76	-
						2,200	2,200	SY	GEOTEXTILE UNDER STONE FILL	649.31	25
						95	95	LB	SEED	651.15	2.7

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: TROY-NEWPORT
PROJECT NUMBER: STP 2613(I)

FILE NAME: 06B056.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET: 06b056*10.i

PLOT DATE: 25-OCT-2011 12:17
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 10 OF 31