QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						800	800	LB	FERTILIZER	651.18	46
						4	4	TON	AGRICULTURAL LIMESTONE	651.20	0.98
						825	825	CY	TOPSOIL	651.35	14
						8,400	8,400	SY	TEMPORARY EROSION MATTING	653.20	278
						143	143	SF	TRAFFIC SIGNS, TYPE A	675.20	1.43
						825	825	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
						68	68	EACH	REMOVING SIGNS	675.50	-
						27	27	EACH	ERECTING SALVAGED SIGNS	675.60	-
						28	28	EACH	DELINEATOR WITH STEEL POST	676.10	-
						28	28	EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-
						1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
						105,000	105,000	SY	SPECIAL PROVISION (COLD MIXED RECYCLED	900.675	1441.13
									BITUMINOUS PAVEMENT, PORTLAND CEMENT)		
						1,600	1,600	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS	900.675	33.3
									CONCRETE MATERIAL, DRIVES)		
						105,000	105,000	SY	SPECIAL PROVISION (RECLAIMED STABILIZED	900.675	2978
									BASE, PORTLAND CEMENT)		
						1,650	1,650	TON	SPECIAL PROVISION (PORTLAND CEMENT	900.680	43
									FOR BASE STABILIZATION)		
						300	300	TON	SPECIAL PROVISION (PORTLAND CEMENT	900.680	3
									FOR COLD MIX RECYCLING)		
						1,300	1,300	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	25

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: TROY-NEWPORT
PROJECT NUMBER: STP 2613(1)

FILE NAME: 06B056.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET: 06b056*11.i

PLOT DATE: 25-OCT-2011 12:17
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 11 OF 31