STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

SEE WO #4 DATED 6-28-10 FOR SIGN CHANGES

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	~~FLANGED CHANNEL~~ REMOVING SIGNS lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA. 105+60 RT NEWPORT	1050 1016 0200	1	6	10	0.42						1		1			X 6.5		X																		E-138
STA. 116+16 LT NEWPORT	1050 1016 0220	1	6	10	0.42						1		1			X 6.5		X																		E-138
STA. 119+69 LT NEWPORT	WEST VERMONT 105	1 1	24 30	12 24	2.00 5.00						1		2			X 13.5		X															GREEN ON WHITE		E-136B
STA. 116+50 RT NEWPORT	NA SPEED LIMIT 35	1	~~36~~	~~36~~	~~9.00~~						~~2~~					~~X~~		~~X~~															W3-5 NOT REPLACED PER WO #4		SHS
STA 120+25 STA 327+20 STA 319+00	NEWPORT CTR POST REMOVAL SHOULDER NARROWS		18	30	3.75								1 1 1			X 11.25																				
STA 124+47 LT	SPEED LIMIT 50		24	30	5.00								1			X 13.75																				
STA 125+20 LT	STOP		30	30	6.25								1			14.25																				
STA 125+20 LT	LAWSON RD				22.84	1 1							1 10			65.75																				
SHEET 27 ~~7~~ 6 TOTAL					25.84		11						17			~~180~~ 162.0																				
SHEET 28 ~~7~~ TOTAL					~~34.59~~	41.26	~~8~~ 6						15			~~195~~ 152.0																				
SHEET 29 ~~8~~ 8 TOTAL					~~31.77~~	56.77	~~5~~ 3						17			~~210~~ 183.75																				
SHEET ~~30~~ 29 TOTAL					~~32.53~~	45.03	~~3~~ 4						19			~~165~~ 145.25																				
SHEET 31 ~~0~~ TOTAL					~~16.84~~	22.84	~~0~~ 1						10			~~75~~ 65.75																				
				SUBTOTAL	191.74 ~~141.57~~		25 ~~27~~					FT	FT EA	FT	FT	FT ~~825~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
				ROUNDING	1.43		-																													
					SF ~~143~~ 191.74	SF	EA. ~~27~~ 25	SF					~~FT~~ EA 78			FT ~~825~~ 708.75				LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 5

PROJECT NAME: TROY-NEWPORT
PROJECT NUMBER: STP 2613(1)

FILE NAME: 06B056.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 06b056*30.i

PLOT DATE: 25-OCT-2011 12:19
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 30 OF 31