QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		GOV'T NON-PARTIC.	FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						70	70	LF	REMOVAL OF EXISTING CURB	616.41	5
						2	2	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.8
						275	275	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	4.40
						505	505	SF	DETECTABLE WARNING SURFACE	618.30	3
						152	152	EACH	YIELDING MARKER POSTS	619.17	–
						245.5	245.5	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	–
						4	4	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	–
						131	131	EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	–
						68	68	EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	–
						237.5	237.5	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	–
						1100	1100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						4200	4200	HR	FLAGGERS	630.15	EST
			1				1	LS	FIELD OFFICE, ENGINEERS	631.10	–
			1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	–
			1				1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	–
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	–
						1	1	LS	TRAFFIC CONTROL	641.10	–
						1	1	LS	PUBLIC RELATIONS OFFICER	641.12	–
						3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	–
						~~40700~~ 43250	~~40700~~ 43250	LF	DURABLE 4" WHITE LINE, THERMOPLASTIC	646.402	300
						~~33350~~ 32250	~~33350~~ 32250	LF	DURABLE 4" YELLOW LINE, THERMOPLASTIC	646.412	180
						~~700~~ 855	~~700~~ 855	LF	DURABLE 8" WHITE LINE, THERMOPLASTIC	646.442	10
						~~630~~ 665	~~630~~ 665	LF	DURABLE 8" YELLOW LINE, THERMOPLASTIC	646.452	5
						820	820	LF	DURABLE 24" STOPBAR, THERMOPLASTIC	646.482	12
						~~354~~ 312	~~354~~ 312	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	–
						1020	1020	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	10
						~~83950~~ 86500	~~83950~~ 86500	LF	TEMPORARY 4" WHITE LINE, PAINT	646.602	528
						~~66700~~ 64500	~~66700~~ 64500	LF	TEMPORARY 4" YELLOW LINE, PAINT	646.612	360
						~~1400~~ 1700	~~1400~~ 1700	LF	TEMPORARY 8" WHITE LINE, PAINT	646.642	10
						~~1260~~ 1330	~~1260~~ 1330	LF	TEMPORARY 8" YELLOW LINE, PAINT	646.652	10
						1640	1640	LF	TEMPORARY 24" STOP BAR, PAINT	646.682	24
						~~708~~ 624	~~708~~ 624	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	–
						2040	2040	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	20
						1930	1930	EA	LINE STRIPING TARGETS	646.76	21
						~~2980~~ 2750	~~2980~~ 2750	LF	PAINTED CURB	646.81	15
						~~2300~~ 1150	~~2300~~ 1150	SF	PAINTED ISLAND	646.82	50
						~~13~~ 5	~~13~~ 5	LB	SEED	651.15	~~0.82~~ 0.45
						~~100~~ 45	~~100~~ 45	LB	FERTILIZER	651.18	5
						1	1	TON	AGRICULTURAL LIMESTONE	651.20	~~0.78~~ 0.84
						~~100~~ 45	~~100~~ 45	CY	TOPSOIL	651.35	~~4.98~~ 1.98

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

NOTE:
REVISIONS IN RED REPRESENT
PROPOSED MODIFICATIONS REQUESTED
BY THE VILLAGE OF ESSEX JUNCTION

* REVISED 02/23/09

PROJECT NAME: COLCHESTER – ESSEX
PROJECT NUMBER: STP 2616 (1)

FILE NAME: p06b062.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #2

PLOT DATE: $$$$DATE$$$
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 6 OF 45

04/13/09