



- 675.50 REMOVING SIGNS
AS SHOWN - 5
- 646.502 DURABLE CROSSWALK MARKING, THERMOPLASTIC
STA. 58+36 LT - 58+80 LT
- 646.702 TEMPORARY CROSSWALK MARKING, PAINT
STA. 58+36 LT - 58+80 LT
- 646.482 DURABLE 24" STOP BAR, THERMOPLASTIC
STA. 58+41 - STA. 58+59 LT
- 646.682 TEMPORARY 24" STOP BAR, PAINT
STA. 58+41 - STA. 58+59 LT
- 646.81 PAINTED CURB
STA. 57+48 - STA. 57+78 RT
(BOTH EDGES OF MEDIAN)

- 203.16 SOLID ROCK EXCAVATION
STA. 58+22 - STA. 58+33 LT
STA. 58+83 - STA. 58+95 LT
- 618.10 PORTLAND CEMENT
CONCRETE SIDEWALK, 5 INCH
STA. 58+22 - STA. 58+33 LT
STA. 58+83 - STA. 58+95 LT
- 618.30 DETECTABLE WARNING SURFACE
STA. 58+25 LT
STA. 58+91 LT

- 646.452 DURABLE 8" YELLOW LINE, THERMOPLASTIC
STA. 57+26 - STA. 58+40 (HATCHED RT)
- 646.652 TEMPORARY 8" YELLOW LINE, PAINT
STA. 57+26 - STA. 58+40 (HATCHED RT)
- 646.402 DURABLE 4" WHITE LINE, THERMOPLASTIC
STA. 56+75 - STA. 62+75 (SOLID LT & RT)
(WITH EDGELINE BREAKS AT WARNER AVE.)
STA. 56+75 - STA. 62+75 (DASHED LT & RT)
- 646.602 TEMPORARY 4" WHITE LINE, PAINT
STA. 56+75 - STA. 62+75 (SOLID LT & RT)
(WITH EDGELINE BREAKS AT WARNER AVE.)
STA. 56+75 - STA. 62+75 (DASHED LT & RT)
- 646.492 DURABLE LETTER OR SYMBOL, THERMOPLASTIC
STA. 58+51 LT "STOP"
- 646.692 TEMPORARY LETTER OR SYMBOL, PAINT
STA. 58+51 LT "STOP"

- 646.412 DURABLE 4" YELLOW LINE, THERMOPLASTIC
STA. 56+75 - STA. 57+78 (SOLID RT, AROUND MEDIAN)
STA. 57+23 - STA. 58+40 (SOLID RT, CENTERLINE)
STA. 57+78 - STA. 58+40 (SOLID RT, CENTERLINE)
STA. 58+59 LT (CENTERLINE WARNER AVE.)
STA. 58+94 - STA. 62+75 (SOLID LT & RT, CENTERLINE)
- 646.612 TEMPORARY 4" YELLOW LINE, PAINT
STA. 56+75 - STA. 57+78 (SOLID RT, AROUND MEDIAN)
STA. 57+23 - STA. 58+40 (SOLID RT, CENTERLINE)
STA. 57+78 - STA. 58+40 (SOLID RT, CENTERLINE)
STA. 58+59 LT (CENTERLINE WARNER AVE.)
STA. 58+94 - STA. 62+75 (SOLID LT & RT, CENTERLINE)
- 604.412, 604.415, 604.418 REHAB, DROP
INLETS, CATCH BASINS, OR MANHOLES, CLASS I,
CLASS II OR CLASS III
- STA. 58+12 RT "TYPE D GRATE"
STA. 58+13 LT "TYPE D GRATE"
STA. 60+17 RT "TYPE D GRATE"
STA. 60+19 LT "TYPE D GRATE"

- 604.42 CHANGING ELEVATION
OF SEWER MANHOLES
STA. 58+60 LT
- 629.20 ADJUST ELEVATION
OF VALVE BOX
STA. 58+48 LT
STA. 58+68 LT

LEGEND		SIGN LEGEND	
⊙	HYDRANT	R	= REMOVE
○	MANHOLE	R&S	= REMOVE AND SALVAGE
⊖	WATER VALVE	RET	= RETAIN
⊙	GAS PIPELINE MARKER	S	= SALVAGE
⊠	CATCH BASIN / DROP INLET	N	= NEW
—	CURB INLET	B-B	= BACK TO BACK
⊠	TRAFFIC CONTROL BOX		
⊕	RAILROAD CROSSING SIGNAL		

SEE REVISED SHEET
NOT TO SCALE

DATUM	
VERTICAL	N/A
HORIZONTAL	N/A

PROJECT LAYOUT SHEET 23	PROJECT NAME: COLCHESTER-ESSEX
	PROJECT NUMBER: STP 2616(I)S
	FILE NAME: p06b062.dgn
	PLOT DATE: 30-OCT-2012 12:00
PROJECT LEADER: EPD	DRAWN BY: SJL
DESIGNED BY: CDL	CHECKED BY: EPD
PLOT FILE: p06b062pl23.i	SHEET 31 OF \$SH\$