STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
STA. ~~75+21 RT~~ 80+00 LT ESSEX	ONLY ELIMINATED	1	30	30	6.25						1					X																	W4-2		E-151
STA. 82+85 RT ESSEX	STATE HIGHWAY BEGINS 0150 0406 0157	1 1 1	30 24 6	30 12 10	6.25 2.00 0.42		1				1					X																	W11-2 FLOURESCENT YELLOW-GREEN TYPE IX SHEETING W16-7p		E-152 E-138
STA. 83+14 LT ESSEX	STATE HIGHWAY ENDS	1 1	30 24	30 12	6.25 2.00		1				1					X																	W11-2 FLOURESCENT YELLOW-GREEN TYPE IX SHEETING W16-7p		E-152
STA 45+86 RT	RIGHT LANE MUST TURN RIGHT	1	30	30	6.25						1					X																			
STA 51+85 RT	(ISLAND)	1 1	24 18	24 18	4.00 2.25						1 1					X X																			
STA 52+99 RT	(ISLAND)	1 1 1	24 18 18	24 18 18	4.00 2.25 2.25						1 1 1					X X X																			
STA 54+42 RT	BIKE LANE AHEAD	1 1	24 24	30 12	5.00 2.00						1 1					X X																			
STA 55+75 RT	BUS STOP						1																												
STA 58+38 LT							4																												
STA 59+06 RT	ONLY	1	30	30	6.25						1					X																			
STA 59+60 RT	BIKE LANE	1	24	30	5.00						1					X																			
STA 60+50 RT	BIKE LANE ENDS	1 1	24 24	30 12	5.00 2.00						1 1					X X																			
STA 66+25 RT	BIKE LANE	1	24	30	5.00						1					X																			
STA 68+60 RT	BEGIN CENTER LANE ONLY	1 1	24 36	12 24	2.00 6.00						1 1					X X																			
	SHEET 37 TOTAL				115.18		3									240																			
	SHEET 38 TOTAL				103.26		5									240																			
	SHEET 39 TOTAL				82.77		5									240																			
	SHEET 40 TOTAL				103.79		0									285																			
	SHEET 41 TOTAL				96.61		1									270																			
	SHEET 42 TOTAL				23.17		2									45																			
	SUBTOTAL				524.78							FT	FT	FT	FT	FT 1320	FT		EA	LB	LB	LB		LB	LB	LB	LB							
	ROUNDING				0.22																														
					SF 525	SF	EA. 16	SF				FT			FT 1320					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 6

PROJECT NAME: COLCHESTER-ESSEX
PROJECT NUMBER: STP 2616(I)S

FILE NAME: p06b062.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p06b062tss6.i

PLOT DATE: 30-OCT-2012 12:0
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 42 OF SH