STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
BRIDGEWATER: 372+24.0, RT	R	1	24	24	4.00						1			X		X		X															SIGN ID CODE R8-3A		E-143
374+89.0, RT	ONLY 25	1	36	36	9.00						2			X																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE W3-5	74	
379+51.0, RT	SPEED LIMIT 25	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
379+51.0, LT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
380+16.0, LT	0040 1405 0720	1	6	10	0.42						1	X			X			X															SIGN ID CODE VD-700		E-138
381+30.0, RT		1	36	36	9.00						2			X																			SIGNS SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS WITH A FLUORESCENT YELLOW-GREEN BACKGROUND SIGN ID CODE SI-1		E-153
	AHEAD	1	30	18	3.75																												SIGN SHALL HAVE A FLUORESCENT YELLOW-GREEN BACKGROUND. SIGN ID CODE W16-9P	74	
383+19.0, LT	NORTH BRIDGEWATER RD TH 3						1				2			X		X		X															SALVAGED SIGN SHALL BE MOUNTED ON TWO NEW POSTS.	-	-
383+28.0, LT	STOP 0040 1405 0726	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
												LF 14.0	LF	LF 70.0 (56.0)	LF 14.0	LF 70.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	SF 42.84	SF	EA. 1	SF	LF 84.0 (56.0)	LF 84.0	LB	EA.	LB	EA.	EA.	LB

TRAFFIC SIGN SUMMARY SHEET #4

PROJECT NAME: BRIDGEWATER--WOODSTOCK
PROJECT NUMBER: NH 26II(I)S

FILE NAME: p06b160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06b160tss04.i
PLOT DATE: 28-MAY-2010
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 51 OF 80