STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
WOODSTOCK: I64+32.0, LT	LEFT LANE MUST TURN LEFT	1	30	30	6.25						1			X		X		X															SIGN ID CODE R3-7L		E-140
I64+36.0, RT	STOP 0040 1424 0311	1 1	30 6	30 10	6.25 0.42						1			X		X		X															BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
I65+80.0, LT	ONLY	1	30	30	6.25						1			X		X		X															SIGN ID CODE VR-92I		E-145A
I65+87.0, RT		1	48	24	8.00						2			X																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE WI-6L		E-152
I66+80.0, RT		1	48	24	8.00						2			X																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE WI-6R		E-152
I68+96.0, LT	0040 1424 0320	1	6	10	0.42						1	X			X			X															SIGN ID CODE VD-700		E-138
I70+61.0, LT	WATCH FOR TURNING VEHICLES	1	36	36	9.00						2			X																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE VW-205		E-154
I71+64.0, RT		1	30	30	6.25						1			X		X		X															SIGN ID CODE WII-6H INSTALL FOLDING SIGN WITH HINGE ASSEMBLY PER STD. E-153. COSTS ASSOCIATED WITH THE HINGE ARE INCIDENTAL TO THE SIGN PANEL.		E-153
												LF 14.0	LF	LF 56.0 (84.0)	LF 14.0	LF 56.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."		**TOTALS**	SF 50.84	SF	EA.	SF		LF 70.0 (84.0)			LF 70.0					LB		EA.	LB				EA.	EA.	LB										

TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: BRIDGEWATER--WOODSTOCK
PROJECT NUMBER: NH 26II(I)S

FILE NAME: p06b160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06b160tss16.i
PLOT DATE: 28-MAY-2010
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 63 OF 80