STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 17

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
WOODSTOCK: 171+74.0, LT	WESTERDALE CUT-OFF TH 28 / WESTERDALE CUT-OFF TH 28						2				1			X		X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1424 0326	1	30	30	6.25																												BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
		1	6	10	0.42																														
172+02.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X																SIGN ID CODE VR-017		E-141
173+20.0, LT		1	30	30	6.25						1			X		X		X																SIGN ID CODE WI-10R	73	
	30 M.P.H.	1	18	18	2.25																												SIGN ID CODE WI3-1		E-155
178+49.0, LT	GABERT RD TH 17 / GABERT RD TH 17						2				1			X		X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1424 0339	1	30	30	6.25																												BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
		1	6	10	0.42																														
179+27.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X																SIGN ID CODE VR-017		E-141
182+32.0, LT		1	30	30	6.25						1			X		X		X																SIGN ID CODE WII-6H INSTALL FOLDING SIGN WITH HINGE ASSEMBLY PER STD. E-153. COSTS ASSOCIATED WITH THE HINGE ARE INCIDENTAL TO THE SIGN PANEL.		E-153
												LF	LF	LF 84.0	LF	LF 84.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 38.09	SF	EA. 4	SF							LF 84.0			LF 84.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #17

PROJECT NAME: BRIDGEWATER--WOODSTOCK
PROJECT NUMBER: NH 26II(I)S

FILE NAME: p06b160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06b160tss17.i
PLOT DATE: 28-MAY-2010
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 64 OF 80