STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
WOODSTOCK: 251+60.0, LT	BIKE ROUTE	1	24	18	3.00						1			X		X		X															SIGN ID CODE D11-1		E-131B
		1	12	9	0.75																											SIGN ID CODE M7-1		E-131B
252+45.0, RT	WATCH FOR TURNING VEHICLES						1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
255+44.0, LT							1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
256+59.0, LT	PROSPER RD TH 03 / PROSPER RD TH 03						2				1			X		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1424 0486	1 1	30 6	30 10	6.25 0.42																											BACK TO BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
256+76.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
	SPEED LIMIT 30	1	24	30	5.00																											SIGN ID CODE R1-1		E-142
256+85.0, LT	THOMAS HILL TH 81 / THOMAS HILL TH 81						2				1			X		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0040 1424 0488	1 1	30 6	30 10	6.25 0.42																											BACK TO BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
												LF	LF	LF 84.0	LF	LF 84.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 27.09	SF	EA. 6	SF							LF 84.0			LF 84.0					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #23

PROJECT NAME: BRIDGEWATER--WOODSTOCK
PROJECT NUMBER: NH 26II(I)S

FILE NAME: p06b160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06b160tss23.i
PLOT DATE: 28-MAY-2010
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 70 OF 80