

QUANTITY SHEET 3



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EP&SC	UTILITIES	279 NB BRIDGE	RAMP A BRIDGE	RAMP D BRIDGE	CHANNEL		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION EE					
264										264		M	600 CAAP 1.52 (68 X 12)	601.0225	-			
264										264		M	600 PCCSP 1.63 (68 X 12)	601.0425	-			
264										264		M	600 RCP CLASS III	601.0825	-			
264										264		M	600 CPEP(SL)	601.2620	-			
													END OPTION EE					
													BEGIN OPTION FF					
203										203		M	750 CAAP 1.91 (68 X 12)	601.0236	-			
203										203		M	750 PCCSP 2.01 (68 X 12)	601.0436	-			
													END OPTION FF					
													BEGIN OPTION GG					
16										16		M	750 CAAP 1.91 (68 X 12)	601.0236	-			
16										16		M	750 PCCSP 2.01 (68 X 12)	601.0436	-			
16										16		M	750 RCP CLASS III	601.0835	-			
16										16		M	750 CPEP(SL)	601.2625	-			
													END OPTION GG					
													BEGIN OPTION HH					
34										34		M	900 CAAP 1.91 (68 X 12)	601.0246	-			
34										34		M	900 PCCSP 2.01 (68 X 12)	601.0446	-			
													END OPTION HH					
													BEGIN OPTION II					
57										57		M	1050 CAAP 2.67 (68 X 12)	601.0252	-			
57										57		M	1050 PCCSP 2.77 (68 X 12)	601.0452	-			
													END OPTION II					
													BEGIN OPTION LL					
2										2		M	1200 CAAP 2.67 (68 X 12)	601.0257	-			
2										2		M	1200 PCCSP 2.77 (68 X 12)	601.0457	-			
													END OPTION LL					
													BEGIN OPTION JJ					
271										271		M	450 RCP CLASS III	601.0815	-			
271										271		M	450 CPEP(SL)	601.2615	-			
													END OPTION JJ					
													BEGIN OPTION KK					
125										125		M	600 RCP CLASS III	601.0825	-			
125										125		M	600 CPEP(SL)	601.2620	-			
													END OPTION KK					
40										40		M	450 CPEP(SL)	601.2615	-			
													BEGIN OPTION AB					
1										1		EACH	600 CSPES 1.63 (68 X 12)	601.6025	-			
1										1		EACH	600 CAAPES 1.52 (68 X 12)	601.6225	-			

PROJECT NAME: **BENNINGTON**
 PROJECT NUMBER: **AC NH 019-1(51)**
 FILE NAME: zd307c1VAOT_Quant.xls PLOT DATE: 04/10/2009
 PROJECT MANAGER: GREG EDWARDS DRAWN BY: STANTEC
 DESIGNED BY: MARC FOISY CHECKED BY: GARY SANTY
 QUANTITY SHEET #3 SHEET 14 OF 367