STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44	50	63	kg/m 2.8	3.2	5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (mm) 75	100.0	100 MOD.	kg/m 1.9	2.5	2.5	FOUNDATION	TUBULAR STEEL dia. (mm) 75	89	100	125	kg/m 11.3	13.4	16.1	21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																																			
VT 279 (CONT.) STA. NB 7+116.7, LT.	2790 0202 0580	1	150	250	0.04						1				3.6					1																							E-138	
STA. NB 7+157.0, RT.	SPEED LIMIT 55	1	900	1200	1.08						1						4.7			1																							R2-1(55)		SHS
STA. NB 7+229.0, LT.		1	900	900	0.81						2				9.7					2																							W4-2R		SHS
STA. NB 7+282.0,RT.	RIGHT LANE ENDS	1	900	900	0.81						2				9.7					2																							W9-1		SHS
STA. NB 7+319.0,LT.	RIGHT LANE ENDS	1	900	900	0.81						2				~~9.7~~ 9.7					2																							W9-1		SHS
STA. NB 7+372.0, RT.		1	900	900	0.81						2				9.7					2																							W4-2R		SHS
STA. NB 7+438.5, RT.	2790 0202 0560	1	150	250	0.04						1				3.7					1																							E-138		
STA. NB 7+580.0, LT.	VERMONT 9 Brattleboro Bennington Downtown Junction 1 MILE	1	4370	4500		19.67					2																													2	861.1	W310x45		TENSION BOLTS TO 160 kN	TSD-02	
STA. NB 7+760.4, LT.	2790 0202 0540	1	150	250	0.04						1				2.9					1																							E-138		
STA. NB 8+082.3, RT.	2790 0202 0520	1	150	250	0.04						1				2.9					1																							E-138		
STA. NB 8+100.0, RT.	SOUTH 7 Bennington Downtown 1 Welcome Center; NORTH 7 Rutland 1 1/2	1	5250	3450		18.11					2																													2	421.1	W250X33		TENSION BOLTS TO 142 kN	TSD-02	
												m 0	m 0	m 0	m 51.9	m 0	m 4.7	EA 13	EA 0	kg 0	kg 0	kg 0		kg 0	kg 0	kg 0	kg 0																		
TOTALS		m^2 4.48	m^2 37.78	EA 0.00	m^2 0.00							m 0.0			m 56.6					kg 0.0			EA	kg 0.0				EA 0.0	EA 4.0	kg 1282.2												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), STANDARD HIGHWAY SIGNS (SHS)

Stantec

PROJECT NAME:	BENNINGTON		
PROJECT NUMBER:	AC NH 019-1(51)		
FILE NAME:	TRAFFIC SIGN SUMMARY.xls	PLOT DATE:	2/3/2009
PROJECT LEADER:	GREG EDWARDS	DRAWN BY:	STANTEC
DESIGNED BY:	MARC FOISY	CHECKED BY:	GARY SANTY
TRAFFIC SIGN SUMMARY SHEET TSS-02		SHEET	127 OF 367