STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RET-AIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (mm) 75 kg/m 1.9	100.0 kg/m 2.5	100 MOD. kg/m 2.5	FOUNDATION	TUBULAR STEEL dia. (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
VT 279 (CONT.) STA. NB 8+240.0, RT.	BRIDGE ICES BEFORE ROAD	1	1200	1200	1.44						2						~~9.7~~ 9.5	2																W8-13		SHS
STA. NB 8+325.0, RT.	BRIDGE 13 VT279	1	150	200	0.03						1				~~3.7~~ 3.1			1																E-134
STA. NB 8+370.0, LT.	BRIDGE 13 VT279	1	150	200	0.03						1				~~3.8~~ 3.1			1																E-134
STA. NB 8+404.2, LT.	2790 0202 0500	1	150	250	0.04						1				3.8			1																E-138
STA. NB 8+500.0, RT.	Old Bennington USE 7 SOUTH	1	4050	1800		7.29					2												2		108.8								TSD-01	
STA. NB 8+533.0, RT.	Furnace Brook / BRIDGE 13 VT279	1 1	850 150	450 200	0.38 0.03						1				4.9			1																TSD-01 E-134
STA. NB 8+694.0, LT.	Furnace Brook / BRIDGE 13 VT279	1 1	850 150	450 200	0.38 0.03						1				4.7			1																TSD-01 E-134
STA. NB 8+702.0, LT.	SLOWER TRAFFIC KEEP RIGHT	1	900	1200	1.08						1						~~5.7~~ 4.5	1																R4-3		SHS
STA. NB 8+726.0, RT.	2790 0202 0480	1	150	250	0.04						1				~~2.9~~ 2.4			1																E-138
STA. NB 8+802.0, LT.		1	900	900	0.81						2				~~9~~ 8.9			2																E-151
STA. NB 8+830.0, RT.		1	900	900	0.81						2				~~9~~ 9.5			2																W6-1		SHS
STA. NB 8+888.0, LT.	BRIDGE ICES BEFORE ROAD	1	1200	1200	1.44						2						~~10~~ 8.9	2																W8-13		SHS
STA. NB 8+890.0, RT.	ALL TRAFFIC	1	900	1200	1.08						1						~~5.1~~ 4.8	1																	TSD-01	
											m 0	m 0	m 0		m 41.8	m 0	m 30.5	EA 16	EA 0	kg 0	kg 0	kg 0		kg 0	kg 108.8	kg 0	kg 0							
TOTALS			m^2 7.62	m^2 7.29	EA 0.00	m^2 0.00						m 0.0			m 72.3					kg 0.0			EA 2.00	kg 108.8				EA 0.00	EA 0.00	kg 0.00					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), STANDARD HIGHWAY SIGNS (SHS)

Stantec

PROJECT NAME:	BENNINGTON		
PROJECT NUMBER:	AC NH 019-1(51)		
FILE NAME:	TRAFFIC SIGN SUMMARY.xls	PLOT DATE:	2/3/2009
PROJECT LEADER:	GREG EDWARDS	DRAWN BY:	STANTEC
DESIGNED BY:	MARC FOISY	CHECKED BY:	GARY SANTY
TRAFFIC SIGN SUMMARY SHEET TSS-03		SHEET 128	OF 367