STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (mm) kg/m 75 1.9	100.0 2.5	100 MOD. 2.5	FOUNDATION	TUBULAR STEEL dia. (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
VT 279 (CONT.) STA. NB 8+957.0, LT.	SPEED LIMIT 55	1	900	1200	1.08						1						~~5~~ 4.6	1																R2-1 (55)		SHS
STA. NB 8+992.0, RT.	SOUTH 7 Bennington Downtown Welcome Center ↓ / TO WEST 279 NORTH 7 Rutland Troy ↓	1 1	3750 3100	5300 4200		19.88 13.02																											ITEM 677.13 - OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	TSD-02 TSD-01	
STA. NB 9+047.4, LT.	2790 0202 0460	1	150	250	0.04						1				~~3.2~~ 2.8			1																E-138	
STA. NB 9+077.0, LT.	GROOVED SHOULDER	1 1	1200 600	1200 450	1.44 0.27						2						~~10.3~~ 9.9	2																TSD-03	E-153B
STA. NB 9+108.0, LT.		1	450	450	0.20						1				~~3.4~~ 3.2			1																OM1-1		SHS
STA. NB 9+130.0, LT.	ALL TRAFFIC B-B	1 1	900 900	1200. 900	1.08 0.81						2				~~9~~ 9.9			2																INSTALL (2) FLASHING BEACONS AS DETAILED ON VTRANS STANDARDS E-109 & E-175 R3-4	TSD-01	SHS
STA. NB 9+160.0, RT.	SPEED LIMIT 55	1	900	1200	1.08						1						~~5.1~~ 4.7	1																R2-1(55)		SHS
STA. NB 9+260.0 LT.-RT.	LEFT SOUTH 7 Bennington Downtown Welcome Center EXIT ONLY / TO WEST 279 NORTH 7 Rutland Troy ↓	1 1 1	1600 3750 3100	700 5300 4200	1.12	19.88 13.02																											ITEM 677.13 - OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	TSD-01 TSD-02 TSD-02	
STA. NB 9+330.0, LT.		1	900	900	0.81						1						~~4.6~~ 4.4	1																R3-4		SHS
STA. NB 9+369.7, RT.	2790 0202 0440	1	150	250	0.04						1				3.1			1																		E-138
STA. NB 9+475.0, RT.	↤ LODGING ↤ FOOD ↤ GAS ↤ PHONE	4	1350	185	0.25						2				8.6			2																		
												m 0	m 0	m 0	m 27.3	m 0	m 25	EA 12	EA 0	kg 0	kg 0	kg 0		kg 0	kg 0	kg 0	kg 0								
TOTALS					m² 8.22	m² 65.80	EA 0.00	m² 0.00				m 0.0			m 52.3					kg 0.0			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), STANDARD HIGHWAY SIGNS (SHS)

Stantec

PROJECT NAME:	BENNINGTON		
PROJECT NUMBER:	AC NH 019-1(51)		
FILE NAME:	TRAFFIC SIGN SUMMARY.xls	PLOT DATE:	2/3/2009
PROJECT LEADER:	GREG EDWARDS	DRAWN BY:	STANTEC
DESIGNED BY:	MARC FOISY	CHECKED BY:	GARY SANTY
TRAFFIC SIGN SUMMARY SHEET TSS-04		SHEET	129 OF 367