STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (mm) 75 kg/m 1.9	100.0 2.5	100 MOD. 2.5	FOUNDATION	TUBULAR STEEL dia. (mm) 75 kg/m 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
VT ROUTE 9 (CONT.)																																			
STA. VT ~~1+345.0, LT.~~ I+324, LT	4.58 TO SOUTH 7 / 4.42 WEST VERMONT 9	1	600	300	0.18						2				~~8.6~~ 9.0			2																M4-5		E-136B
		1	600	600	0.36																														E-136B
		1	600	300	0.18																												M3-3		SHS
		1	600	300	0.18																												M1-4		SHS
		1	600	600	0.36																														SHS
STA. VT 1+350.0, RT.	ONLY	1	750	750	0.56						1				3.8			1																		E-145A
STA. VT 1+420.0, RT.	4.63 WEST VERMONT 279 / TO 7 / EAST VERMONT 9	1	600	300.	0.18						2						~~7.8~~ 9.6	2																M4-5		E-136B
		1	750	600	0.45																														E-136B
		1	525	375	0.20																														E-136B
		1	600	300	0.18																												M4-5		SHS
		1	600	600	0.36																												M1-4		SHS
		1	525	375	0.20																												M6-1		SHS
		1	600	300	0.18																														E-136B
		1	600	600	0.36																														E-136B
		1	525	375	0.20																														E-136B
STA. VT 1+446.3, LT.		1	450	450	0.20						1				2.9			1																OM1-1		SHS
STA. VT 1+490.6, LT.		1	450	450	0.20						1				~~3~~ 2.77			1																OM1-1		SHS
STA. VT 1+517.5, RT.		1	750	750	0.56						1				3.8			1																	TSD-03	
STA. VT 1+540.0, LT.	H	1	600	600	0.36						1				~~3.7~~ 4.04			1																D9-2		SHS
		1	525	375	0.20																												M6-3 (INTERSTATE)		SHS
STA. VT 1+540.0, LT.	WEST VERMONT 9 / TO SOUTH 7 / WEST VERMONT 279 / TO NORTH 7	1	600	300	0.18						2													2	98.3								M4-5		E-136B
		1	600	600	0.36																														E-136B
		1	525	375	0.20																														E-136B
		1	600	300	0.18																												M4-5		SHS
		1	600	300	0.18																												M3-3		SHS
		1	600	600	0.36																												M1-4		SHS
		1	525	375	0.20																												M6-3		SHS
		1	600	300	0.18																														E-136B
		1	600	600	0.36																														E-136B
		1	525	375	0.20																														E-136B
		1	600	300	0.18																												M4-5		SHS
		1	600	300	0.18																												M3-1		SHS
		1	750	600.	0.45																												M1-4		SHS
		1	525	375	0.20																												M6-1		SHS
STA. VT 1+557.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS / NO OUTLET	1	600	750	0.45		1				1						~~4.5~~ 5.0	1																INSTALL SALVAGED NO OUTLET SIGN BELOW THE NEW LEGAL LOAD SIGN ON NEW POST		E-141
STA. VT 1+570.0, RT.	HARVARD ST / STOP / B-B / 0090 0202 0388	1	750	750	0.56		1				1					4.1		1																R1-1		SHS
		1	150	250	0.04																												MOUNT NEW STOP SIGN AND REFERENCE PLAQUE BACK-TO-BACK. INSTALL SALVAGED STREET SIGN 150 ABOVE THE STOP SIGN USING POST TOP MOUNTING BRACKET ON A NEW POST.		E-138
												m 0	m 0	m 0	m 25.8	m 4.1	m 12.3	EA 11	EA 0	kg 0	kg 0	kg 0		kg 98.3	kg 0	kg 0	kg 0								
TOTALS		m^2 10.11	m^2 0.00	EA 2.00	m^2 0.00							m 0.0			m 42.2					kg 0			EA 2	kg 98.3				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), STANDARD HIGHWAY SIGNS (SHS)

Stantec

PROJECT NAME:	BENNINGTON
PROJECT NUMBER:	AC NH 019-1(51)
FILE NAME:	TRAFFIC SIGN SUMMARY.xls
PROJECT LEADER:	GREG EDWARDS
DESIGNED BY:	MARC FOISY
TRAFFIC SIGN SUMMARY SHEET TSS-09	
PLOT DATE:	2/3/2009
DRAWN BY:	STANTEC
CHECKED BY:	GARY SANTY
SHEET	134 OF 367