STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia. (mm) 75 kg/m 1.9	100.0 kg/m 2.5	100 MOD. kg/m 2.5	FOUNDATION	TUBULAR STEEL dia. (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																										
VT ROUTE 9 (CONT.) STA. VT 1+575.0, RT.		1	750	750	0.56						1				~~3.8~~ 3.81			1																		E-145A
STA. VT 1+590.0, LT.	BENNINGTON 1	1	1800	300	0.54						2					8.2		2																		E-123
	TROY NY 33	1	1800	300	0.54																															E-123
	RUTLAND 55	1	1800	300	0.54																															E-123
STA. VT ~~1+620.0, RT.~~ I+645, RT	STATE HIGHWAY BEGINS VT I+200, RT SPEED LIMIT 40	1	600	750	0.45						1					~~4.4~~ 3.81		1																	R2-1(30)		E-141
		1	600	450	0.27																															SHS
STA. VT ~~1+620.0, LT.~~ I+645, LT	STATE HIGHWAY ENDS VT I+200, LT SPEED LIMIT 30	1	600	750	0.45						1					~~4.4~~ 5.09		1																	R2-1(30)		E-141
		1	600	450	0.27																															SHS
STA. VT 1+646.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS NO OUTLET						1				1						~~4.5~~ 4.87	1																INSTALL SALVAGED LEGAL LOAD LIMIT SIGN ABOVE NEW NO OUTLET SIGN ON NEW POST W14-2		
		1	750	750	0.56																															SHS
STA. VT 1+658.0, RT.	HICKORY HILL STOP B-B 0098 0302 0592						1				1					~~4.1~~ 3.8		1																	R1-1 MOUNT NEW STOP SIGN AND REFERENCE PLAQUE BACK -TO -BACK. INSTALL SALVAGED STREET SIGN 150 ABOVE THE STOP SIGN USING POST TOP MOUNTING BRACKET ON A NEW POST.		SHS
		1	750	750	0.56																															E-138
		1	150	250	0.04																															
STA. VT 1+662.5, RT.	EAST 9	1	525	375	0.20						1				~~3.9~~ 4.47			1																			E-136B
		1	600	600	0.36																															E-136B
STA. VT 1+662.5, LT.	WEST 279 NEXT RIGHT FOLLOW WEST Bennington Downtown 9	1	2250	2250		5.06					2												2	88.8										TSD-03	
STA. VT 1+690.0, RT.	WILMINGTON 21	1	1800	300	0.54						2				~~7.5~~ 8.62			2																		E-123
	BRATTLEBORO 38	1	1800	300	0.54																															E-123
STA. VT 1+724.0, LT.	BENNINGTON OLD BENNINGTON 3	1	750	450	0.34						1				~~3.6~~ 4.0			1																		E-128A&B
STA. VT 1+739.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS NO OUTLET	1	600	750	0.45						1						~~4.6~~ 5.18	1																W14-2		E-141
		1	750	750	0.56																															SHS
STA. VT 1+751.0, RT.	LINDEN ST STOP						1				1						~~4.5~~ 4.11	1																R1-1 INSTALL SALVAGED STREET SIGN 150 ABOVE THE STOP SIGN USING POST TOP MOUNTING BRACKET ON A NEW POST.		SHS
		1	750	750	0.56																															
STA. VT ~~1+766.0, LT.~~ I+787, RT	ONTRAVELED LANE	1	600	750	0.45						1				4.2			1																		TSD-01	
STA. VT 1+770.0, LT.		1	900	900	0.81						2				8.7			2																W3-3		SHS
												m 0	m 0	m 0	m 31.7	m 21.1	m 13.6	EA 16	EA 0	kg 0	kg 0	kg 0		kg 88.8	kg 0	kg 0	kg 0							
TOTALS			m^2 9.59	m^2 5.06	EA 3.00	m^2 0.00						m 0.0			m 66.4					kg 0.0			EA 2	kg 88.8				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), STANDARD HIGHWAY SIGNS (SHS)

Stantec

PROJECT NAME:	BENNINGTON
PROJECT NUMBER:	AC NH 019-1(51)
FILE NAME:	TRAFFIC SIGN SUMMARY.xls
PROJECT LEADER:	GREG EDWARDS
DESIGNED BY:	MARC FOISY
TRAFFIC SIGN SUMMARY SHEET TSS-10	
PLOT DATE:	2/3/2009
DRAWN BY:	STANTEC
CHECKED BY:	GARY SANTY
SHEET	135 OF 367