STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 01

Metric

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (mm) 44	50	63 kg/m 2.8	3.6	5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia.(mm) 75	100.0	100 MOD kg/m 1.9	2.5	2.5	TUBULAR STEEL dia.(mm) FOUNDATION	75	89	100	125 kg/m 11.3	13.4	16.1	21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT 279 WEST BOUND																																									
WB 9+770.0		1	1800	750	1.35	8-13-12																																MINIMUM TYPE IX LEGEND, MINIMUM TYPE IX BACKGROUND	TSD-01	
		1	3750	5100		19.13	8-13-12																																MINIMUM TYPE IX LEGEND, MINIMUM TYPE IX BACKGROUND	TSD-01	
																																							INSTALL SIGNS ON AN OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT. REFER TO OVERHEAD SIGN DETAIL SHEETS FOR INSTALLATION.		
		1	3100	4200		13.02	8-13-12																																MINIMUM TYPE IX LEGEND, MINIMUM TYPE IX BACKGROUND	TSD-01	
WB 9+833.5, LT.		1	1500	1500		2.25	8-8-12				2														2	90 ~~103.5~~ 5-30-12												MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND	TSD-01	
		1	450	450	0.20	8-8-12																		5-24-12														OMI-1, MINIMUM TYPE III SHEETING		SHS
		1	450	450	0.20																																	OMI-1, MINIMUM TYPE III SHEETING		SHS
WB 9+900.0, RT.		1	900	900	0.81	7-30-12					2			9.5 ~~9.3~~ 7-30-12				2																						W4-6, MINIMUM TYPE III SHEETING		SHS

NOTES:
1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."
2. ALL OVERHEAD GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE IX BACKGROUND. ALL GROUND MOUNTED GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE III BACKGROUND. ALL CHEVRON SIGNS SHALL HAVE TYPE IX SHEETING. ALL OTHER GROUND MOUNTED SIGNS SHALL HAVE A MINIMUM TYPE III SHEETING.

		m	m 9.3	m		EA	kg	kg	kg		kg ~~103.5~~ 90	kg	kg	kg																											
SHEET TOTALS		m^2 2.56	m^2 34.4	EA.	m^2		m ~~9.3~~ 9.5				kg				EA. 2	kg ~~103.5~~ 90				EA.	EA.	kg																			

SHS = STANDARD HIGHWAY SIGNS MANUAL

Stantec

PROJECT NAME: BENNINGTON
PROJECT NUMBER: NH 019-1(54)

FILE NAME: ...\plot_files\zd307c4tss.ptf
DESIGN SUPERVISOR: GREG EDWARDS
DESIGNED BY: MARC FOISY
TRAFFIC SIGN SUMMARY SHEET TSS-01

PLOT DATE: 1/26/2010
DRAWN BY: STANTEC
CHECKED BY: GARY SANTY
SHEET 186 OF 468

1/26/2010 4:51:06 PM v:\1953\active\195310002\transportation\drawing\contract 4\plot_files\zd307c4tss.ptf