STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 09

MUTCD Metric

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.6	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia.(mm) 75 kg/m 1.9	100.0 kg/m 2.5	100 MOD kg/m 2.5	FOUND-ATION	TUBULAR STEEL dia.(mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
RAMP R (CONT.)																																
R 1+103.0, RT.		1	900	780	0.35	8-1-12					1		4.1 ~~4.3~~ 8-1-12		1															RI-2, MINIMUM TYPE III SHEETING		SHS
R 1+115.0, LT.	ONE WAY	1	900	300	0.27	8-9-12					1		3.7 8-9-12		1															R6-1R, MINIMUM TYPE III SHEETING		SHS
RAMP S S 2+067.0, RT.		1	900	780	0.35	8-1-12					1		4.1 ~~4.3~~ 8-1-12		1															RI-2, MINIMUM TYPE III SHEETING		SHS
RAMP T T 1+064.0, LT.		1	900	900	0.81	8-1-12					2		9.3 ~~8.7~~ 8-1-12		2															W3-2, MINIMUM TYPE III SHEETING		SHS
T 1+121.0, RT.		1	900	780	0.35	8-1-12					1		4.4 ~~4.3~~ 8-1-12		1															RI-2, MINIMUM TYPE III SHEETING		SHS
RAMP U U 1+020.0, LT.	EAST VERMONT 279	1 1 1	600 750 525	300 600 375	0.18 0.45 0.20	8-8-12					1			4.9 ~~4.7~~ 8-8-12	1															M3-2, MINIMUM TYPE III SHEETING MI-5, MINIMUM TYPE III SHEETING M6-2, MINIMUM TYPE III SHEETING		E-136B E-136B E-136B
U 1+200.0, RT.		1	900	900	0.81	8-2-12					2		9.1 ~~8.8~~ 8-2-12		2															W4-3R, MINIMUM TYPE III SHEETING		SHS
U 1+305.0, LT.	ONE WAY	1	900	300	0.27	8-8-12					1		3.9 ~~3.6~~ 8-8-12		1															R6-1R, MINIMUM TYPE III SHEETING		SHS

NOTES:
1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."
2. ALL OVERHEAD GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE IX BACKGROUND. ALL GROUND MOUNTED GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE III BACKGROUND. ALL CHEVRON SIGNS SHALL HAVE TYPE IX SHEETING. ALL OTHER GROUND MOUNTED SIGNS SHALL HAVE A MINIMUM TYPE III SHEETING.

SHS = STANDARD HIGHWAY SIGNS MANUAL

											m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
											0	~~37.7~~ 38.6	~~4.7~~ 4.9																				
SHEET TOTALS		m^2	m^2	EA.	m^2						m					kg			EA.	kg				EA.	EA.	kg						
		4.04									~~42.4~~ 43.5																					

Stantec

PROJECT NAME: BENNINGTON
PROJECT NUMBER: NH 019-1(54)

FILE NAME: ...\plot_files\zd307c4tss.ptf
DESIGN SUPERVISOR: GREG EDWARDS
DESIGNED BY: MARC FOISY
TRAFFIC SIGN SUMMARY SHEET TSS-09

PLOT DATE: 1/26/2010
DRAWN BY: STANTEC
CHECKED BY: GARY SANTY
SHEET 194 OF 468

1/26/2010 4:51:7 PM v:\1953\active\19531002\transportation\drawing\contract 4\plot_files\zd307c4tss.ptf