STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

VTrans Metric

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: SQUARE STEEL (mm) 44 / 50 / 63 kg/m 2.8 / 3.6 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia.(mm) 75 / 100.0 / 100 MOD kg/m 1.9 / 2.5 / 2.5	TUBULAR STEEL dia.(mm) FOUNDATION	75 / 89 / 100 / 125 kg/m 11.3 / 13.4 / 16.1 / 21.8	W-SHAPE STEEL FTG. SIZE 600 mm / 750 mm	WEIGHT	POST SIZE	SIGN REMOVED & REINSTALLED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 279																									
MM 2.00, RT.	HISTORIC TO VT 7A North Bennington 1 MILE	1	8250	3900		32.18	6-15-12		X															MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND MOUNT NEW SIGN ON EXISTING W-SHAPE STEEL SIGN SUPPORTS.	TSD-06	
MM 2.30, RT.	Bennington College NEXT RIGHT	1	4950	1050		5.20	6-15-12				2									2	366 ~~462.4~~	W200X27		MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND	TSD-06	
	Bennington Downtown USE 7 SOUTH	1	4950	1500		7.43														8-4-11				MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND POST DESIGN FOR THIS SIGN WAS BASED ON APPROXIMATE TOPOGRAPHIC DATA. CONTRACTOR TO VERIFY REQUIRED POST DESIGN PRIOR TO FABRICATION.	TSD-07	
MM 2.50, RT.	HISTORIC VT 67A TO VT 7A ½ NORTH 7 Welcome Center 1 SOUTH 7 BENNINGTON 1 ¼	1	~~8400~~ 6450	5100		~~42.84~~ 32.90	8-6-12				3									3	1070 ~~1240.2~~	W310X45		MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND POST DESIGN FOR THIS SIGN WAS BASED ON APPROXIMATE TOPOGRAPHIC DATA. CONTRACTOR TO VERIFY REQUIRED POST DESIGN PRIOR TO FABRICATION.	TSD-07	
																				8-4-11					
MM 2.57, RT.	SOUTH VT 67A OR 7	1	3000	3150		9.45	6-15-12				2									2	344 ~~409.4~~	W200X27		MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND POST DESIGN FOR THIS SIGN WAS BASED ON APPROXIMATE TOPOGRAPHIC DATA. CONTRACTOR TO VERIFY REQUIRED POST DESIGN PRIOR TO FABRICATION.	TSD-07	
																				8-4-11					
MM 2.70, RT.	EXIT HISTORIC VT 67A TO VT 7A North Bennington ↗	1	1360	750	1.02	6-15-12					3									3	624 ~~757.5~~	W200X31		MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND POST DESIGN FOR THIS SIGN WAS BASED ON APPROXIMATE TOPOGRAPHIC DATA. CONTRACTOR TO VERIFY REQUIRED POST DESIGN PRIOR TO FABRICATION.	TSD-07	
		1	9450	3000		28.35	6-15-12													8-4-11				MINIMUM TYPE IX LEGEND, MINIMUM TYPE III BACKGROUND	TSD-07	
MM 3.00, LT-RT	EAST TO VT 279 7 Brattleboro Rutland ↓ HISTORIC VT 67A TO VT 7A North Bennington EXIT ↗ ONLY	1	3750	3900		14.63	5-16-12																	MINIMUM TYPE IX LEGEND, MINIMUM TYPE IX BACKGROUND INSTALL SIGNS ON AN OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT. REFER TO OVERHEAD SIGN DETAIL SHEETS FOR INSTALLATION.	TSD-08	
		1	5550	3300		18.32	5-16-12																	MINIMUM TYPE IX LEGEND, MINIMUM TYPE IX BACKGROUND	TSD-08	
SHEET TOTALS					m² 1.02	m² ~~148.46~~ 158.4	EA.	m²			m 0		kg		EA.		kg			EA. 7	EA. 3	kg ~~2869.5~~ 2404				

SHS = STANDARD HIGHWAY SIGNS MANUAL

NOTES:

1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."
2. ALL OVERHEAD GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE IX BACKGROUND. ALL GROUND MOUNTED GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE III BACKGROUND. ALL CHEVRON SIGNS SHALL HAVE TYPE IX SHEETING. ALL OTHER GROUND MOUNTED SIGNS SHALL HAVE A MINIMUM TYPE III SHEETING.

Stantec

PROJECT NAME: BENNINGTON
PROJECT NUMBER: NH 019-1(54)

FILE NAME: ...\plot_files\zd307c4tss.ptf
DESIGN SUPERVISOR: GREG EDWARDS
DESIGNED BY: MARC FOISY
TRAFFIC SIGN SUMMARY SHEET TSS-16

PLOT DATE: 1/26/2010
DRAWN BY: STANTEC
CHECKED BY: GARY SANTY
SHEET 201 OF 468

1/26/2010 4:51:29 PM v:\1953\active\195310002\transportation\drawing\contract 4\plot_files\zd307c4tss.ptf