



**INDEX OF SHEETS**

BR800	PRELIMINARY INFORMATION SHEET
BR801	TYPICAL BRIDGE SECTIONS
BR802	BRIDGE QUANTITY SHEET
BR803	PLAN
BR804	ELEVATION
BR805	HIGHWAY PROFILES
BR806	GENERAL NOTES
BR807	EXPANSION JOINT PLANS
BR808	EXPANSION JOINT DETAIL SHEET 1
BR809	EXPANSION JOINT DETAIL SHEET 2
BR810	DOWNSPOUT DETAILS
BR811	CURB DETAILS
BR812	CONCRETE MEDIAN BARRIER DETAILS
BR813	REINFORCEMENT AND RAILING PLAN
BR814	BRIDGE RAILING - NETC 2 RAIL
BR815	APPROACH RAILING
BR816	DETAILS - NETC 2 RAIL
BR817	SNOW FENCE - NETC 2 RAIL
BR818	REINFORCING STEEL SCHEDULE

**ESTIMATED TRAFFIC DATA**  
RAMP G/S OVER VT ROUTE 279 2030 ADT : 4380

**HYDROLOGIC DATA**

DRAINAGE AREA= \_\_\_\_\_  
 CHARACTER OF TERRAIN= \_\_\_\_\_  
 CHARACTER & TYPE OF STREAM= \_\_\_\_\_  
 NATURE OF STREAMBED= \_\_\_\_\_

Q2.33= \_\_\_\_\_ cms      Q50= \_\_\_\_\_ cms  
 Q10= \_\_\_\_\_ cms      Q100= \_\_\_\_\_ cms  
 Q25= \_\_\_\_\_ cms      Q500= \_\_\_\_\_ cms

DATE OF FLOOD OF RECORD= \_\_\_\_\_  
 WATER SURFACE ELEV. # \_\_\_\_\_ ESTIMATED DISCHARGE# \_\_\_\_\_  
 NATURAL STREAM VELOCITY @ Q50 = \_\_\_\_\_ mps  
 ICE CONDITIONS# \_\_\_\_\_ DEBRIS# \_\_\_\_\_  
 DOES THE STREAM REACH MAXIMUM HIGHWATER ELEVATION RAPIDLY? \_\_\_\_\_  
 IS ORDINARY BASE RAPID? \_\_\_\_\_  
 IS STAGE AFFECTED BY UPSTREAM OR DOWNSTREAM CONDITIONS? \_\_\_\_\_  
 IF YES, DESCRIBE. \_\_\_\_\_

WATERSHED STORAGE \_\_\_\_\_ HEADWATERS \_\_\_\_\_ UNIFORM THROUGHOUT WATERSHED \_\_\_\_\_  
 IMMEDIATELY ABOVE SITE \_\_\_\_\_

**EXISTING STRUCTURE**

STRUCTURE TYPE# Two span contin. curved plate girder bridge YEAR BUILT# 1973  
 CLEAR SPAN (NORMAL TO STREAM)# \_\_\_\_\_ N/A  
 VERTICAL CLEARANCE ABOVE STREAMBED# \_\_\_\_\_ N/A  
 WATERWAY OF FULL OPENING# \_\_\_\_\_ N/A  
 DISPOSITION OF STRUCTURE# \_\_\_\_\_ N/A

TYPE OF MATERIAL UNDER SUBSTRUCTURE# \_\_\_\_\_ N/A

WATER SURFACE ELEV. @ Q2.33= \_\_\_\_\_ VELOCITY# \_\_\_\_\_ mps  
 Q10= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q25= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q50= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q100= \_\_\_\_\_ " \_\_\_\_\_ mps

LONG TERM STREAM BED CHANGES# \_\_\_\_\_ N/A

IS THE ROADWAY OVERTOPPED BELOW THE Q100? N/A FREQUENCY# N/A  
 RELIEF ELEVATION# N/A DISCHARGE OVER ROAD @ Q100# N/A

UPSTREAM STRUCTURE# TOWN# \_\_\_\_\_ N/A DISTANCE# \_\_\_\_\_  
 HIGHWAY NO.# \_\_\_\_\_ STRUCTURE NO.# \_\_\_\_\_  
 STRUCTURE TYPE# \_\_\_\_\_  
 CLEAR SPAN# \_\_\_\_\_ CLEAR HEIGHT# \_\_\_\_\_  
 YEAR BUILT# \_\_\_\_\_ FULL WATERWAY# \_\_\_\_\_

DOWNSTREAM STRUCTURE# TOWN# \_\_\_\_\_ N/A DISTANCE# \_\_\_\_\_  
 HIGHWAY NO.# \_\_\_\_\_ STRUCTURE NO.# \_\_\_\_\_  
 STRUCTURE TYPE# \_\_\_\_\_  
 CLEAR SPAN# \_\_\_\_\_ CLEAR HEIGHT# \_\_\_\_\_  
 YEAR BUILT# \_\_\_\_\_ FULL WATERWAY# \_\_\_\_\_

**PROPOSED STRUCTURE**

STRUCTURE TYPE# \_\_\_\_\_ N/A  
 CLEAR SPAN (NORMAL TO STREAM)# \_\_\_\_\_ N/A  
 VERTICAL CLEARANCE ABOVE STREAMBED# \_\_\_\_\_ N/A  
 WATERWAY OF FULL OPENING# \_\_\_\_\_ N/A

WATER SURFACE ELEV. @ Q2.33= \_\_\_\_\_ VELOCITY# \_\_\_\_\_ mps  
 Q10= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q25= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q50= \_\_\_\_\_ " \_\_\_\_\_ mps  
 Q100= \_\_\_\_\_ " \_\_\_\_\_ mps

IS THE ROADWAY OVERTOPPED BELOW THE Q100? N/A FREQUENCY# N/A  
 RELIEF ELEVATION# N/A DISCHARGE OVER ROAD @ Q100# N/A

AVERAGE LOW ELEVATION OF SUPERSTRUCTURE# \_\_\_\_\_  
 VERTICAL CLEARANCE @ Q 100 = \_\_\_\_\_ m

SCOUR# Channel = \_\_\_\_\_ N/A  
 REQUIRED CHANNEL PROTECTION# \_\_\_\_\_ N/A

**PERMIT INFORMATION**

AVERAGE DAILY FLOW# \_\_\_\_\_ N/A  
 ORDINARY LOW WATER# \_\_\_\_\_ cms \_\_\_\_\_ ELEV.# \_\_\_\_\_  
 ORDINARY HIGH WATER# \_\_\_\_\_ cms \_\_\_\_\_ ELEV.# \_\_\_\_\_

**TEMPORARY BRIDGE REQUIREMENTS**

STRUCTURE TYPE# \_\_\_\_\_ N/A  
 CLEAR SPAN (NORMAL TO STREAM)# \_\_\_\_\_ N/A  
 VERTICAL CLEARANCE ABOVE STREAMBED# \_\_\_\_\_ N/A  
 WATERWAY OF FULL OPENING# \_\_\_\_\_ N/A

**DESIGN CRITERIA#**

- DESIGN LIVE LOAD AASHTO MS-18
- DESIGN SPAN \_\_\_\_\_ 32,900 m + 36,600 m = 69,500 m
- ALLOWABLE LOAD FOR SPREAD FOOTINGS ON SOIL \_\_\_\_\_ ON LEDGE \_\_\_\_\_ N/A
- ALLOWABLE LOAD FOR PILING \_\_\_\_\_ TYPE \_\_\_\_\_ N/A ESTIMATED LENGTH \_\_\_\_\_ N/A
- STRUCTURAL STEEL AASHTO GRADE AASHTO M 270M, GRADE 250
- REINFORCING STEEL GRADE 420
- CONCRETE, HIGH PERFORMANCE CLASS A  $f_c$  : 30 MPa
- CONCRETE, HIGH PERFORMANCE CLASS B  $f_c$  : N/A
- DESIGN METHOD \_\_\_\_\_

**TRAFFIC MAINTENANCE#**

- IS TRAFFIC TO BE MAINTAINED? YES \_\_\_\_\_ IF YES, ON EXISTING STRUCTURE \_\_\_\_\_ NO \_\_\_\_\_ OR ON TEMPORARY BRIDGE \_\_\_\_\_ N/A
- TEMPORARY BRIDGE REQUIREMENTS# ONE OR TWO WAY \_\_\_\_\_ N/A TRAFFIC CONTROL SIGNALS REQUIRED \_\_\_\_\_ N/A

MINIMUM CLEAR SPAN (NORMAL TO STREAM)# \_\_\_\_\_ N/A VERTICAL CLEARANCE ABOVE STREAMBED# \_\_\_\_\_ N/A  
 WATERWAY AT FULL OPENING# \_\_\_\_\_ N/A  
 ARE SIDEWALKS REQUIRED? \_\_\_\_\_ N/A IF SO, ON WHAT SIDE? \_\_\_\_\_ N/A

**LOAD FACTOR LOAD RATING (LFD) (METRIC TONS)**

LOADING LEVELS (LOAD FACTOR)	TRUCK				
	M	MS	3S2	6 AXLE	3A, STR. 4A, STR. 5A, SEMI
INVENTORY A=2.17# B=1.00					
POSTED A=1.55# B=1.40					
OPERATING A=1.30# B=1.67					

STRENGTH RF =  $\frac{0.95 M_N - 1.3 M_{DL}}{A \times M_{LL+1}}$  SERVICEABILITY RF = B  $\frac{.95 F_y S_{LL+1} - M_{DL} \frac{S_{LL+1}}{S_m} - M_{SOL} \frac{S_{LL+1}}{S_{sol}}}{1.67 M_{LL+1}}$

**NOTE:**  
ALL DIMENSIONS ARE IN MILLIMETERS (mm)  
UNLESS OTHERWISE NOTED.



**STATE OF VERMONT  
AGENCY OF TRANSPORTATION**

Town Of **BENNINGTON** Bridge No. **14A**  
 Highway No. \_\_\_\_\_ Log Sta. \_\_\_\_\_  
 \_\_\_\_\_ Surv. Sta. \_\_\_\_\_

**RAMP G/S OVER VT ROUTE 279 WB**

**PRELIMINARY INFORMATION SHEET**

Designed By **M. CHENETTE** Drawn By **A. THIBAUT**  
 Checked By \_\_\_\_\_ Date \_\_\_\_\_ Bridge Design Supervisor  
**M. CHENETTE** 11/09 **G. BOGUE** Date 11/09

PROJECT **BENNINGTON** PROJECT NO. **NH F019-(154)**

L.G.C. info  
 Bridge Sheet No. BR800 Sheet 275 of 468

I:\25\2800\_454\3 PM\_VA\953\active\953\002\structure\design\del\7\p101 - file\BR800-SRAMP05-PI511.rvt