RECORD PLANS

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (MM)	HEIGHT (MM)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (MM) 44 (KG /M) 2.8	SQUARE STEEL (MM) 50 (KG /M) 3.2	SQUARE STEEL (MM) 63 (KG /M) 5.0	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 (KG /M) 11.30	TUBULAR STEEL Ø (mm) 89 (KG /M) 13.40	TUBULAR STEEL Ø (mm) 100 (KG /M) 16.10	TUBULAR STEEL Ø (mm) 125 (KG /M) 21.70	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BENNINGTON VT67A NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.185	F	M2-1	525	375		JCT						1		X														
		F	M1-5A	600	600		HISTORIC 7A (JCT)						1							Existing Removed									
		F	M4-6	600	300		END (END)						1							4 ea. 9-26-12									
		F	M1-5A	600	600		VT 67A						1																
SB	0.140	F	D1-1A	1800 ~~1200~~	300			0.54 ~~0.36~~								2	9-26-12		10.3 ~~X~~						BEHIND GUARDRAIL SO SOIL BEARING SLIP BASES ARE NOT REQUIRED		2	
		F	D1-1A	1800 ~~1200~~	300			0.54 ~~0.36~~																			2	
		F	D1-1A	1800 1200	300			0.54 0.36																			2	
		F	M2-1	525	375		Bennington 2	0.20																	GREEN ON WHITE	X		
		F	VM-078	600	300		Arlington 13	0.18																	GREEN ON WHITE		2	
		F	M1-5A	600	600		Manchester 21 / JCT / HISTORIC / END	0.36																				E-136B
		F	M4-6	600	300		VERMONT 7A / VERMONT 67A	0.18																	GREEN ON WHITE SHEETING	X		
		F	M1-5A	600	600		9-26-12	0.36																				E-136B
SB	0.130	F	D1-1A	1200	250		DESTINATION SIGNS						1		X					Existing Removed									
		F	D1-1A	1200	250		Bennington 2						1							3 ea 9-26-12									
		F	D1-1A	1200	250		Arlington 13 / Manchester 21						1																
SIGN SUMMARY SHEET							SHEET TOTALS	2.36	0.00	0	0	0	7	0	2	2	9.2			0	0.0	0.0	0.0	0.0					
								SM	SM	EA	EA	EA	EA	EA	EA	EA	M			EA	KG	KG	KG	KG					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	5.83	0.0	1	6	6	27	2	5	6	27.6			0		0.0							

PROJECT NAME: Bennington
PROJECT NUMBER: NH 019-1(54)
FILE NAME: Bennington VT67A.xls
PROJECT MANAGER: 0
DESIGNED BY: T. Guazzoni
BENNINGTON VT67A SHEET 2
PLOT DATE: 3/7/2012
DRAWN BY: T. Guazzoni
CHECKED 0
SHEET 2 OF 4