COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2626(I)				STP 2622(I)		SUMMARY OF ESTIMATED QUANTITIES				
NON-PARTICIPATING	BRIDGE	FULL C.E.	ROADWAY	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			10		20	30	CY	COMMON EXCAVATION	203.15	
			1		1	2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
			58,000		10,450	68,450	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	
			80		20	100	TON	SUBBASE, RAP	301.40	
			240		45	285	CWT	EMULSIFIED ASPHALT	404.65	
			1		1	2	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
			6600		1250	7850	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	
			1		1	2	LU	AIR VOIDS PAY ADJUSTMEMT (N.A.B.I.)	490.31	
			1			1	LU	MAT DENSITY PAY ADJUSTMEMT (N.A.B.I.)	490.32	
			1			1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	
			1			1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	
	135					135	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	
	50					50	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	
			12		1	13	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	
			11		1	12	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	
			11		1	12	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	
19					12	31	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	
			175		50	225	HR	POWER GRADER RENTAL	608.15	
			50		20	70	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
			125		20	145	HR	POWER BROOM RENTAL, TYPE I	608.30	
			300		30	330	HR	POWER BROOM RENTAL, TYPE II	608.31	
			150		30	180	HR	TRUCK RENTAL	608.37	
			125		30	155	HR	LOADER RENTAL, TYPE I	608.40	
			2			2	CY	STONE FILL, TYPE I	613.10	
			30		60	90	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	
			10		55	65	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	
			20		100	120	SF	DETECTABLE WARNING SURFACE	618.30	
			25		5	30	EA	YIELDING MARKER POSTS	619.17	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

COMPOSITE QUANTITY SHEET #1

PROJECT NAME: BENNINGTON & BENNINGTON (NORTH BENNINGTON) CLASS I

PROJECT NUMBER: STP 2626(I) & STP 2622(I)

FILE NAME: p06b220.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
DWG. NO. p06b220cquant.i

PLOT DATE: 07-MAY-2012 14:2
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 3 OF 69